# Additional Subsurface Investigation Report

CHA Project Number: 8423

Prepared for:



1405 Brewerton Road · Syracuse, NY 13208 · 315-454-4467 · www.solventsandpetroleum.com

Prepared by:

CHA 441 South Salina Street

Syracuse, New York 13202 Phone: (315) 471-3920 Fax: (315) 471-3569

February 28, 2014

I:\8423\Reports\Additional Facility Investigation\Subsurface Investigation Report\2014 Subsurface Investigation Report.doc



## TABLE OF CONTENTS

1.0	Intro	duction	1
	1.1	Site History	1
		Site Geology	
2.0	Scop	e of Work	3
	2.1	Subsurface Investigation	3
	2.2	Semi-Annual Groundwater Monitoring	4
3.0	Field	l Observations	5
4.0	Anal	ytical Results	6
5.0	Conc	clusions	7

## LIST OF FIGURES

Figure 1. Site Location Map

Figure 2. Boring Location Map

Figure 3. Concentration vs. Time- MW-1S

## **LIST OF APPENDICES**

Appendix A. Field Logs

Appendix B Laboratory Data



#### 1.0 INTRODUCTION

Groundwater monitoring has been ongoing at the Solvents and Petroleum Service's Inc. (SPS) facility located at 1405 Brewerton Road in Syracuse, New York for approximately 20 years. In 2006, monitoring was discontinued in two (2) out of the four (4) on-site monitoring wells. Based upon the review of all data available for the site, the site setting, and the low threat to human health and the environment, on behalf of SPS, CHA requested in April 2013 that the remaining groundwater monitoring program be terminated and that no further action be required. Additional questions were raised by the New York State Department of Environmental Conservation (NYSDEC), particularly in regard to the source of contamination observed in well MW-1S. In response, CHA, on behalf of SPS, prepared a Work Plan that was reviewed and approved by the NYSDEC. CHA implemented the work plan on December 16, 2013, focused on an area up-gradient of this well. A site location map is included as Figure 1.

#### 1.1 SITE HISTORY

Historically, solvents and petroleum products have been handled at the property located at 1405 Brewerton Road in the Town of Salina, New York since the 1950s. A gasoline station was also located on site from approximately the 1940s to the early 1970s. Reportedly, the underground storage tanks associated with the gasoline storage were removed at the time the station was closed.

Solvents and Petroleum Service purchased the property in 1977. Since that time, SPS has been a distributor of virgin solvents. In 1979, SPS expanded their business to collect and store spent solvents. These materials are classified as hazardous wastes. No disposal of hazardous wastes occurs on site.

There have been no reported releases of hazardous substances in the last five years. In fact, SPS has had no reportable releases since 1988. The releases which occurred prior to 1988 involved less than 100 gallons of solvents and SPS made efforts to contain and cleanup the spills. Because of these reported spills and the historical uses of the property, the impact to groundwater quality has been under investigation since the early 1990s.



#### 1.2 SITE GEOLOGY

The site geology has been investigated and summarized in a number of previous reports. Most portions of the site are underlain by fill. Where fill materials are absent, the subsurface deposits consist of silts and fine sands to a depth of approximately 20 feet below grade at the southern portion of the site (MW-1S) and up to 30 feet below grade at the northern end of the site. A dense glacial till underlies the silt and sand deposits encountered at that depth. Depth to groundwater on the SPS site is approximately 4 to 5 feet below grade. The till is considered to have a very low permeability. Previous investigations on the site also indicate that groundwater velocity beneath the site is relatively slow at approximately 35 feet/year. Groundwater primarily flows in a northwesterly direction across the site toward Old Ley Creek.



#### 2.0 SCOPE OF WORK

#### 2.1 SUBSURFACE INVESTIGATION

To investigate the potential for an up-gradient source of contamination, CHA planned to advance 4 soil borings on the east side of Brewerton Road. Because this property is privately owned, CHA planned to conduct the investigation in the Right of Way controlled by the New York State Department of Transportation. A temporary high way work permit was granted by the NYSDOT.

CHA retained NYEG Drilling LLC of Brewerton, New York to perform the drilling work. A total of four (4) soil borings were advanced using hydraulic push (Geoprobe®) drilling techniques to a maximum depth of 16 feet below ground surface (bgs). It is noted that refusal was encountered at 12 feet at two (2) locations due to very compact soils. Soil samples were collected continuously and screened in the field for visual, olfactory, and photoionic evidence of contamination.

A total of four (4) soil samples were collected from the site and submitted to TestAmerica Analytical Laboratories (TAL) in Amherst, NY (NYS ELAP Certification# 10026) for analysis of Target Compound List (TCL) volatile organic compounds (VOCs) and MTBE via EPA Method 8260, and TCL semi-volatile organic compounds (SVOCs) via EPA Method 8270. It is important to note that historically, the primary contaminants detected in well MW-1S included benzene, toluene, ethylbenzene, and total xylenes (BTEX). No quality assurance/quality control (QA/QC) samples were required by the NYSDEC for this monitoring event with the exception of one trip blank collected for VOC analysis.

All non-disposable, down-hole equipment (e.g. MacroCore® sampler) was decontaminated between sampling locations to prevent possible cross-contamination. Decontamination water was discharged onto the ground.

After the collection of the soil sample, the borings were converted to temporary monitoring wells which were constructed with one-inch diameter PVC riser pipe and well screen. The well screens had a slot opening size of 0.010-inches and the screen was inserted directly into the open boring to collect a groundwater sample. CHA collected one (1) groundwater sample from each well using disposable polyethylene and silicone tubing and a peristaltic pump the same day that the wells were installed. The wells were not purged and there were no groundwater quality parameters collected due



to the temporary nature of the wells. The groundwater samples were analyzed for the same VOC and SVOC parameters as the soil samples. No quality assurance/quality control (QA/QC) samples were required by the NYSDEC for this monitoring event with the exception of one trip blank collected for VOC analysis.

The locations of the borings and groundwater monitoring wells are shown on Figure 2 (attached).

#### 2.2 SEMI-ANNUAL GROUNDWATER MONITORING

At the same time the investigation was being conducted on the east side of Brewerton Road, CHA also conducted the winter semi-annual groundwater monitoring event at the existing SPS facility. That work is summarized in a report submitted under separate cover.



#### 3.0 FIELD OBSERVATIONS

The soils observed in the four borings were noted to be primarily sand and silt with gravel observed in the upper layers. The soils became denser and more compact with depth. Groundwater was generally encountered at approximately four (4) feet bgs during drilling activities. The boring logs for the site are included as Attachment A.

During the course of the boring and well installations, there was no significant evidence of fill material, nor was there any visual, olfactory, or photoionic evidence of soil contamination in the onsite borings. Photoionization detector (PID) readings for both direct readings off of the soil samples and headspace readings were all 0.0 parts per million (ppm).

The water removed from the temporary monitoring wells was observed to be very turbid, however there was no odor or sheen observed, and no formal well development or purging occurred.



#### 4.0 ANALYTICAL RESULTS

Tables 1 and 2 summarize the soil and groundwater results as compared to applicable NYS cleanup standards and guidance values. Only the detected compounds are displayed in the tables. The full laboratory data package is included as Appendix B.

The soil results were compared to NYSDEC CP-51 Soil Cleanup Objectives (SCOs). Specifically, CP-51 - Table 2 (utilized for gasoline release sites) was referenced due to the documented petroleum contamination on the adjacent site.

**Table 1: Soil Sample Results- Detects Only** 

				Bor	ing	
Parameter	units	CP-51 Standard	TW-1	TW-2	TW-3	TW-4
methylene chloride	μg/kg	na	16	16	17	16

**Table 2: Groundwater Sample Results- Detects Only** 

				Tempora	ary Well	
Parameter	units	TOGS 1.1.1 Class GA Groundwater Standard	TW-1	TW-2	TW-3	TW-4
acetone	μg/l	50	ND	10	ND	ND

As shown in Tables 1 and 2 above, the only detected parameter in the soil was methylene chloride and only acetone was detected in the groundwater. Methylene chloride does not have an applicable CP-51 SCO assigned. The detection of acetone in the groundwater sample is below NYSDEC TOGS 1.1.1 Class GA groundwater standards. Additionally, both of these parameters are likely the result of laboratory contamination, rather than reflective of field conditions. The laboratory analytical results support the field observations that there is no evidence of significant petroleum contamination in any of the borings/monitoring wells installed as part of the subsurface investigation.



#### 5.0 CONCLUSIONS

Based on the results of this investigation, it appears that the petroleum contamination observed in well MW-1S on the SPS site does not originate from an upgradient source. While the source of the contamination remains uncertain, it is possible that the contamination is associated with the historic presence of underground storage tanks that were removed prior to 1977.

The other pertinent information regarding contamination in MW-1S includes:

- No petroleum compounds have been detected in down-gradient well MW-4R indicating contamination from MW-1S has not reached the perimeter of the site.
- The site is mostly paved with asphalt or concrete and is underlain by low porosity soils consisting of silt and find sands to a depth of 20-30 feet bgs, that lies above dense glacial till. These conditions inhibit the movement of contaminants through the site soils.
- There are no sensitive receptors in the area with the exception of Old Ley Creek and again, petroleum contamination has not been detected in down-gradient well MW-4R. Natural attenuation is effectively decreasing contaminants presence in the groundwater at locations MW-1S. Total BTEX concentrations have decreased by approximately 75% since the beginning of monitoring activities.
- The concentration of individual BTEX contaminants have shown either a decreasing trend or a stable trend (See Figure 3).

In conclusion, the contamination observed in well MW-1S appears to be the result of historic sources, removed prior to 1977 and the residual contamination continues to slowly attenuate. With no apparent migration off of the property, there is no threat to the environment. SPS again petitions NYSDEC to terminate monitoring of this well.



## **FIGURES**



SOURCE: Bing Maps



MAP NOT TO SCALE

DATE: November 2013

FIGURE 1
Site Location
SOLVENTS AND PETROLEUM SERVICES INC.
1405 BREWERTON ROAD
TOWN OF SALINA
ONONDAGA COUNTY, STATE OF NEW YORK



SOURCE: NYS Orthos Online



441 South Salina Street, Syracuse, NY 13202-4712 www.chacompanies.com

NOT TO SCALE

DATE: January 2014

# Figure 2 Boring and Temporary Monitoring Well Location Map

Solvents and Petroleum Services Inc.




Figure 3



## **Appendix A: Field Logs**

	<u>C</u> t	<del>A</del>					TEST B	ORII	ΝG	LOG		BORING NO.	TW-1	
PROJECT CLIENT:	& LOCAT	ION: Brewe	erton Roants	ad- Rigi Petrolei	ht of W	ay Inve	estigation					PROJECT NO.	· 8423 40'	30
CONTRAC		NYEG	ì									SHEET NO.:		50
	GROUNI	DWATER M	DEPTH					CASI	NG	SAMPLER	CORE BARREL	ELEVATION:		
DATE 1/16/14	TIME 1310	WATER 3.44 bgs	BOTT CAS	OM OF SING	BOTTO BOR	ING	TYPE: SIZE I.D.:					START DATE:	1/16/14	TIME: 840
1, 10, 11	1010	0.11.090			·		HAMMER WT.:							
							HAMMER FALL:					FINISH DATE:		TIME: 940
							DRILL FLUID:		DEPTH	HINTRODUCED:		RIG TYPE: Geo	oprobe	
							CHECKED BY:					DRILLER: Jay	Maitland	
	IF BORING	3 IS DRY, C		HERE:			DATE:	1				INSPECTOR: [	D. Benati	
DEPTH IN FEET	SAMPLE NO.	RECOVERY LENGTH	SPT BLOWS PER 6"	PID R (Pi	eading PM)	(Evide	NOTES ence of Contam.)			FII	ELD CLASSII	FICATION		
_	S1	3.8/4'	NA		0 = 0 = 0			Stain	ing, g ' bgs	grey, moist, SILT AND	loose	tr. silt, clay		
— 5 — —	<b>S</b> 2	4/4'	NA		0 = 0 = 0			brow	n w/tr	n <u>SAND</u> , So r. rust, wet 4' bgs	me Silt, tr.	sand, tr. cla	ay, redo	dish
1	S3	4/4'	NA		0 = 0 = 0				bgs <u>f</u>			wn, wet, loo eddish brow		st,
1 15	S4	4/4'			0 = 0 = 0			13-16	3'bgs			rown, loose, tr. clay, redd		own,
								EO		16 feet BC	GS			
		g:	% [	⊠ Yes Time	s □ No e: <u>930</u>	) Dep	ected: oth: <u>4 ft.</u> to <u>5 f</u>	<u>t.</u> Tii 15	Yes	Sample Col □ No <u> 320</u> Scree			RING NO	O. TW-1

	Ct	₩					TEST B	ORIN	G I	LOG		BORING N	IO. TW-2	
PROJECT	T & LOCAT	TON: Brewe	erton Roants			/ay Inve	estigation					DDO IECT	NO - 9422 4020	
CONTRA	CTOR:	NYEG		Petrolei	um								NO.: 8423.4030 D.: 1 OF 1	
		DWATER M	/IEASUR					CASING	2	SAMPLER	CORE			
DATE	TIME	WATER	DEPTH BOTT	OM OF	BOTT	OM OF	TYPE:	CASINO	,	JAINII LEIK	BARREL	ELEVATIO	ON:	
1/16/14	1430	2.41		SING 2		RING 12	SIZE I.D.:					START DA	ATE: 1/16/14 TIME:	945
							HAMMER WT.: HAMMER FALL:					FINISH DA	ATE: 1/16/14 TIME:	: 1215
							DRILL FLUID:	DE	EPTH	I INTRODUCED:		RIG TYPE	: Geoprobe	
							CHECKED BY:					DRILLER:	Jay Maitland	
	IF BORING	G IS DRY, C	CHECK H	HERE:			DATE:					INSPECTO	OR: D. Benati	
DEPTH IN FEET	SAMPLE NO.	RECOVERY LENGTH	SPT BLOWS PER 6"	PID Re		(Evide	NOTES ence of Contam.)			FIE	ELD CLASSIF			
	S1	3/4'	NA	PID	= 0		·	asphalt	, bll s <u>fm</u>	k staining, one SAND A	gray, moist	, loose (1	ay, tr. silt, tr. fill) eddish brown,	
5	S2	4/4'	NA	PID HS				loose (t	ill) s <u>Sa</u>	nc SAND, li ame as abo und 4 ft. bgs	ove, moist,	•	dish brown, we	·t,
1	<b>S</b> 3	4/4'	NA	PID HS				10-12' k	ogs ated	ame as abo same as a d @ 12 ft., o ue to compa	<u>bove,</u> mois driller indic	st, very c	ompact ould be difficult	t to
15								EOB	= 1	2 feet BO	SS			
	s Readin	_	%   [	⊠Yes Γime: Sampl	□ No <u>1145</u> led du	Deptue to s	ected: th: <u>2</u> to <u>4'</u> staining on soil	⊠ Ye Time s <u>bgs</u>	es	Sample Coll □ No 400 Scree			BORING NO.	TW-2

	<u>C</u> t	A				TEST B	ORING	LOG		BORING NO. TW-3	
PROJECT CLIENT:	T & LOCAT	ION: Brew		ad- Right o Petroleum	Way Inv	estigation				PROJECT NO.: 8423.403	Λ
CONTRA	CTOR:	NYEC		elioleuili						SHEET NO.: 1 OF 1	U
		DWATER N		EMENT TO (FT.):		-	CASING	SAMPLER	CORE BARREL	ELEVATION:	
DATE	TIME	WATER	CAS	SING	TTOM OF BORING	TYPE:				CTART RATE 4/4/44	TIME 4045
1/16/14	1545	0.7	1	3	16	SIZE I.D.: HAMMER WT.:				START DATE: 1/16/14	TIME: 1315
						HAMMER FALL:				FINISH DATE: 1/16/14	TIME: 1400
						DRILL FLUID:	DEF	TH INTRODUCED:		RIG TYPE: Geoprobe	
						CHECKED BY:				DRILLER: Jay Maitland	
	1	3 IS DRY, (		IERE: 🗌		DATE:				INSPECTOR: D. Benati	
DEPTH IN FEET	SAMPLE NO.	RECOVERY LENGTH	SPT BLOWS PER 6"	PID Readin (PPM)		NOTES ence of Contam.)		FI	ELD CLASSIF	ICATION	
	S1	1.5/4'	NA	PID = (			_			SOIL vel, tr. silt, tr. clay,	brown,
5 	S2	2/4'	NA	PID = 0			staining,	grey, wet, lo	ose (fill)	and, tr. silt, tr. clay, el, tr. silt, tr. clay, re	
1	\$3	4/4'	NA	PID = (			wet, loos 9.5' – 12	e	ID AND SIL	<u>VEL</u> , tr. silt, tr. cla <u>T</u> , tr. gravel, tr. cla act (till)	
15	<b>S</b> 4	4/4'	NA	PID = (				bgs fall bac bgs <u>same as</u>			
							EOB	= 16 feet E	GS		
Soil Ga	s Readin	g:		Soil Sam ⊠ Yes □ Time	No	ected: Depth: <u>4</u> to <u>6</u>	⊠ Ye	r Sample Co s □ No : <u>1530</u> Scre js		3 to BORING NO.	. TW-3

	<u>C</u> t	A				TEST B	ORIN	G	LOG		BORIN	IG NO. TW-4	
PROJECT	T & LOCAT	TON: Brew		ad- Right o Petroleum	of Way Inv	estigation					PR∩IE	ECT NO.: 8423.403	Λ
CONTRA	CTOR:	NYEC	3	elioleuiii							SHEET	TNO.: 1 OF 1	U
		DWATER N	MEASURI DEPTH	EMENT TO (FT.):		-	CASING	;	SAMPLER	CORE BARREL	ELEVA	ATION:	
DATE	TIME	WATER	CAS	SING	OTTOM OF BORING	TYPE:					07407		TILLE 1.100
1/16/14 1/16/14	1550 1600	7.72 7.62		2	12 12	SIZE I.D.: HAMMER WT.:					START	Γ DATE: 1/16/14	TIME: 1430
						HAMMER FALL:					FINISH	H DATE: 1/16/14	TIME: 1520
						DRILL FLUID:	DE	PTH	I INTRODUCED:		RIG TY	YPE: Geoprobe	
						CHECKED BY:					DRILLE	ER: Jay Maitland	
1		G IS DRY, (				DATE:					INSPE	CTOR: D. Benati	
DEPTH IN FEET	SAMPLE NO.	RECOVERY LENGTH	SPT BLOWS PER 6"	PID Readii (PPM)		NOTES ence of Contam.)			FII	ELD CLASSIF	FICATIO	NC	
_	<b>S</b> 1	3/4'	NA	PID = HS = 0			0.5-3'bg	js <u>f</u>	TOPSOIL fmc SAND / root stainin	AND SILT,		y, tr. gravel, ı ct	reddish
5 	<b>S</b> 2	4/4'	NA	PID = HS = 0					<u>nc SAND,</u> li ist, very co		clay, tr	r. gravel, redo	dish
1	\$3	4/4'	NA	PID =			8-12' bç	gs <u>s</u>	same as ab	<u>ove</u>			
1 5									12 feet B d extremely			•	
20													
Soil Ga	s Readin	g:		Soil San ⊠ Yes □ Time	No	ected: Depth: <u>3</u> to <u>4</u>	⊠ Y	es [ e: <u>1</u>	Sample Col □ No <u>550</u> Scree		2 to	BORING NO	. TW-4



## **Appendix B: Laboratory Data**



THE LEADER IN ENVIRONMENTAL TESTING

## ANALYTICAL REPORT

TestAmerica Laboratories, Inc.

TestAmerica Buffalo 10 Hazelwood Drive Amherst, NY 14228-2298 Tel: (716)691-2600


TestAmerica Job ID: 480-53428-1

Client Project/Site: Solvents and Petroleum

For:

CHA Inc 441 South Salina Street Syracuse, New York 13202

Attn: Katie E Flood



Authorized for release by: 1/27/2014 10:17:14 AM

Peggy Gray-Erdmann, Client Relations Manager (716)504-9829

peggy.gray-erdmann@testamericainc.com

·····LINKS ·······

Review your project results through

Total Access

**Have a Question?** 



Visit us at: www.testamericainc.com The test results in this report meet all 2003 NELAC and 2009 TNI requirements for accredited parameters, exceptions are noted in this report. This report may not be reproduced except in full, and with written approval from the laboratory. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory. FOIL199418

# **Table of Contents**

Cover Page	1
Table of Contents	2
Definitions/Glossary	3
Case Narrative	4
Detection Summary	5
Client Sample Results	6
Surrogate Summary	13
QC Sample Results	14
QC Association Summary	17
Lab Chronicle	18
Certification Summary	19
Method Summary	20
Sample Summary	21
Chain of Custody	22
Receipt Checklists	23

3

4

6

8

9

11

13

14

15

## **Definitions/Glossary**

Client: CHA Inc TestAmerica Job ID: 480-53428-1

Project/Site: Solvents and Petroleum

#### **Qualifiers**

#### **GC/MS VOA**

Qualifier **Qualifier Description** 

LCS or LCSD exceeds the control limits

#### **Glossary**

Abbreviation	These commonly used abbreviations may or may not be present in this report.
	Listed under the "D" solumn to design to that the result is reported an a dry weight b

column to designate that the result is reported on a dry weight basis

%R Percent Recovery **CNF** Contains no Free Liquid

DER Duplicate error ratio (normalized absolute difference)

Dil Fac Dilution Factor

DL, RA, RE, IN Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample

DLC Decision level concentration MDA Minimum detectable activity EDL **Estimated Detection Limit** MDC Minimum detectable concentration MDL Method Detection Limit

Minimum Level (Dioxin) ML NC Not Calculated

ND Not detected at the reporting limit (or MDL or EDL if shown)

**PQL Practical Quantitation Limit** 

QC **Quality Control** RER Relative error ratio

RL Reporting Limit or Requested Limit (Radiochemistry)

**RPD** Relative Percent Difference, a measure of the relative difference between two points

TEF Toxicity Equivalent Factor (Dioxin) TEQ Toxicity Equivalent Quotient (Dioxin)

#### **Case Narrative**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-1

Job ID: 480-53428-1

Laboratory: TestAmerica Buffalo

Narrative

Job Narrative 480-53428-1

#### Comments

No additional comments.

#### Receipt

The samples were received on 1/17/2014 1:00 AM; the samples arrived in good condition, properly preserved and, where required, on ice. The temperatures of the 2 coolers at receipt time were 3.5° C and 3.7° C.

#### GC/MS VOA

Method(s) 8260C: The large number of analytes included in the continuing calibration verification (CCV) in batch 162441 gives a high probability that one or more analytes will be outside acceptance criteria. As indicated in the reference method, analysis may proceed as long as no more than 20% of the analytes are outside the method-defined %D criteria.

Method(s) 8260C: The laboratory control sample (LCS) and / or laboratory control sample duplicate (LCSD) for batch 162441 recovered outside control limits for the following analytes: 2-Hexanone. These analytes were biased high in the LCS and were not detected in the associated samples; therefore, the data have been reported.

Method(s) 8260C: The following sample(s) were collected in properly preserved vials for analysis of volatile organic compounds (VOCs). However, the pH was outside the required criteria when verified by the laboratory, and corrective action was not possible: TW-1 (480-53428-3).

No other analytical or quality issues were noted.

4

\_

e

7

8

9

11

14

1/

15

#### **Detection Summary**

Client: CHA Inc TestAn Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-1

Lab Sample ID: 480-53428-3

No Detections.

**Client Sample ID: TW-1** 

Client Sample ID: TW-2 Lab Sample ID: 480-53428-4

 Analyte
 Result
 Qualifier
 RL
 MDL
 Unit
 Dil Fac
 D
 Method
 Prep Type

 Acetone
 10
 10
 ug/L
 1
 8260C
 Total/NA

Client Sample ID: TW-3 Lab Sample ID: 480-53428-5

No Detections.

Client Sample ID: TW-4 Lab Sample ID: 480-53428-6

No Detections.

Client Sample ID: Trip Blank Lab Sample ID: 480-53428-11

No Detections.

This Detection Summary does not include radiochemical test results.

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-1

Lab Sample ID: 480-53428-3

Matrix: Water

Date Collected: 01/16/14 13:20 Date Received: 01/17/14 01:00

**Client Sample ID: TW-1** 

Analyte	Result Qualifier	RL	MDL Unit	D Prepared	Analyzed	Dil Fa
1,1,1-Trichloroethane	ND —	1.0	ug/L		01/21/14 02:00	
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L		01/21/14 02:00	
1,1,2-Trichloroethane	ND	1.0	ug/L		01/21/14 02:00	
1,1,2-Trichloro-1,2,2-trifluoroethane	ND	1.0	ug/L		01/21/14 02:00	
1,1-Dichloroethane	ND	1.0	ug/L		01/21/14 02:00	
1,1-Dichloroethene	ND	1.0	ug/L		01/21/14 02:00	
1,2,4-Trichlorobenzene	ND	1.0	ug/L		01/21/14 02:00	
1,2-Dibromo-3-Chloropropane	ND	1.0	ug/L		01/21/14 02:00	
1,2-Dichlorobenzene	ND	1.0	ug/L		01/21/14 02:00	
1,2-Dichloroethane	ND	1.0	ug/L		01/21/14 02:00	
1,2-Dichloropropane	ND	1.0	ug/L		01/21/14 02:00	
1,3-Dichlorobenzene	ND	1.0	ug/L		01/21/14 02:00	
1,4-Dichlorobenzene	ND	1.0	ug/L		01/21/14 02:00	
2-Butanone (MEK)	ND	10	ug/L		01/21/14 02:00	
2-Hexanone	ND *	5.0	ug/L		01/21/14 02:00	
4-Methyl-2-pentanone (MIBK)	ND	5.0	ug/L		01/21/14 02:00	
Acetone	ND	10	ug/L		01/21/14 02:00	
Benzene	ND	1.0	ug/L		01/21/14 02:00	
Bromodichloromethane	ND	1.0	ug/L		01/21/14 02:00	
Bromoform	ND	1.0	ug/L		01/21/14 02:00	
Bromomethane	ND	1.0	ug/L		01/21/14 02:00	
Carbon disulfide	ND	1.0	ug/L		01/21/14 02:00	
Carbon tetrachloride	ND	1.0	ug/L		01/21/14 02:00	
Chlorobenzene	ND	1.0	ug/L		01/21/14 02:00	
Dibromochloromethane	ND	1.0	ug/L		01/21/14 02:00	
Chloroethane	ND	1.0	ug/L		01/21/14 02:00	
Chloroform	ND	1.0	ug/L		01/21/14 02:00	
Chloromethane	ND	1.0	ug/L		01/21/14 02:00	
cis-1,2-Dichloroethene	ND	1.0	ug/L		01/21/14 02:00	
cis-1,3-Dichloropropene	ND	1.0	ug/L		01/21/14 02:00	
Cyclohexane	ND	1.0	ug/L		01/21/14 02:00	
Dichlorodifluoromethane	ND	1.0	ug/L		01/21/14 02:00	
Ethylbenzene	ND	1.0	ug/L		01/21/14 02:00	
1,2-Dibromoethane	ND	1.0	ug/L		01/21/14 02:00	
Isopropylbenzene	ND	1.0	ug/L		01/21/14 02:00	
Methyl acetate	ND	1.0	ug/L		01/21/14 02:00	
Methyl tert-butyl ether	ND	1.0	ug/L		01/21/14 02:00	
Methylcyclohexane	ND	1.0	ug/L		01/21/14 02:00	
Methylene Chloride	ND	1.0	ug/L		01/21/14 02:00	
Styrene	ND	1.0	ug/L		01/21/14 02:00	
Tetrachloroethene	ND	1.0	ug/L		01/21/14 02:00	
Toluene	ND	1.0	ug/L		01/21/14 02:00	
trans-1,2-Dichloroethene	ND	1.0	ug/L		01/21/14 02:00	
trans-1,3-Dichloropropene	ND	1.0	ug/L		01/21/14 02:00	
Trichloroethene	ND	1.0	ug/L		01/21/14 02:00	
Trichlorofluoromethane	ND	1.0	ug/L		01/21/14 02:00	
Vinyl chloride	ND ND	1.0	ug/L		01/21/14 02:00	
Xylenes, Total	ND ND	2.0	ug/L ug/L		01/21/14 02:00	

TestAmerica Buffalo

FOIL199423 1/27/2014

Client: CHA Inc

Project/Site: Solvents and Petroleum

Lab Sample ID: 480-53428-3

TestAmerica Job ID: 480-53428-1

Matrix: Water

Client Sample ID: TW-1

Date Collected: 01/16/14 13:20 Date Received: 01/17/14 01:00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	96		71 - 126		01/21/14 02:00	1
1,2-Dichloroethane-d4 (Surr)	95		66 - 137		01/21/14 02:00	1
4-Bromofluorobenzene (Surr)	113		73 - 120		01/21/14 02:00	1

Client Sample ID: TW-2 Lab Sample ID: 480-53428-4

Date Collected: 01/16/14 14:00 Matrix: Water

Date Received: 01/17/14 01:00

Analyte	Result Qualifier	RL	MDL Unit	D Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND -	1.0	ug/L		01/21/14 02:25	1
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L		01/21/14 02:25	1
1,1,2-Trichloroethane	ND	1.0	ug/L		01/21/14 02:25	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND	1.0	ug/L		01/21/14 02:25	1
1,1-Dichloroethane	ND	1.0	ug/L		01/21/14 02:25	1
1,1-Dichloroethene	ND	1.0	ug/L		01/21/14 02:25	1
1,2,4-Trichlorobenzene	ND	1.0	ug/L		01/21/14 02:25	1
1,2-Dibromo-3-Chloropropane	ND	1.0	ug/L		01/21/14 02:25	1
1,2-Dichlorobenzene	ND	1.0	ug/L		01/21/14 02:25	1
1,2-Dichloroethane	ND	1.0	ug/L		01/21/14 02:25	1
1,2-Dichloropropane	ND	1.0	ug/L		01/21/14 02:25	1
1,3-Dichlorobenzene	ND	1.0	ug/L		01/21/14 02:25	1
1,4-Dichlorobenzene	ND	1.0	ug/L		01/21/14 02:25	1
2-Butanone (MEK)	ND	10	ug/L		01/21/14 02:25	1
2-Hexanone	ND *	5.0	ug/L		01/21/14 02:25	1
4-Methyl-2-pentanone (MIBK)	ND	5.0	ug/L		01/21/14 02:25	1
Acetone	10	10	ug/L		01/21/14 02:25	1
Benzene	ND	1.0	ug/L		01/21/14 02:25	1
Bromodichloromethane	ND	1.0	ug/L		01/21/14 02:25	1
Bromoform	ND	1.0	ug/L		01/21/14 02:25	1
Bromomethane	ND	1.0	ug/L		01/21/14 02:25	1
Carbon disulfide	ND	1.0	ug/L		01/21/14 02:25	1
Carbon tetrachloride	ND	1.0	ug/L		01/21/14 02:25	1
Chlorobenzene	ND	1.0	ug/L		01/21/14 02:25	1
Dibromochloromethane	ND	1.0	ug/L		01/21/14 02:25	
Chloroethane	ND	1.0	ug/L		01/21/14 02:25	1
Chloroform	ND	1.0	ug/L		01/21/14 02:25	1
Chloromethane	ND	1.0	ug/L		01/21/14 02:25	1
cis-1,2-Dichloroethene	ND	1.0	ug/L		01/21/14 02:25	1
cis-1,3-Dichloropropene	ND	1.0	ug/L		01/21/14 02:25	1
Cyclohexane	ND	1.0	ug/L		01/21/14 02:25	1
Dichlorodifluoromethane	ND	1.0	ug/L		01/21/14 02:25	1
Ethylbenzene	ND	1.0	ug/L		01/21/14 02:25	1
1,2-Dibromoethane	ND	1.0	ug/L		01/21/14 02:25	1
Isopropylbenzene	ND	1.0	ug/L		01/21/14 02:25	1
Methyl acetate	ND	1.0	ug/L		01/21/14 02:25	1
Methyl tert-butyl ether	ND	1.0	ug/L ug/L		01/21/14 02:25	' 1
Methylcyclohexane	ND	1.0	ug/L		01/21/14 02:25	1
Methylene Chloride	ND	1.0	ug/L		01/21/14 02:25	1
Styrene	ND	1.0	ug/L ug/L		01/21/14 02:25	' 1

TestAmerica Buffalo

FOIL199424 1/27/2014

Page 7 of 23

2

3

5

6

9

14

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-1

**Client Sample ID: TW-2** 

Lab Sample ID: 480-53428-4 Date Collected: 01/16/14 14:00

Matrix: Water

Date Received: 01/17/14 01:00

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Tetrachloroethene	ND		1.0		ug/L			01/21/14 02:25	1
Toluene	ND		1.0		ug/L			01/21/14 02:25	1
trans-1,2-Dichloroethene	ND		1.0		ug/L			01/21/14 02:25	1
trans-1,3-Dichloropropene	ND		1.0		ug/L			01/21/14 02:25	1
Trichloroethene	ND		1.0		ug/L			01/21/14 02:25	1
Trichlorofluoromethane	ND		1.0		ug/L			01/21/14 02:25	1
Vinyl chloride	ND		1.0		ug/L			01/21/14 02:25	1
Xylenes, Total	ND		2.0		ug/L			01/21/14 02:25	1
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	96		71 - 126			_		01/21/14 02:25	1
1,2-Dichloroethane-d4 (Surr)	95		66 - 137					01/21/14 02:25	1
4-Bromofluorobenzene (Surr)	114		73 - 120					01/21/14 02:25	1

**Client Sample ID: TW-3** Lab Sample ID: 480-53428-5

Date Collected: 01/16/14 15:30 Matrix: Water

Date Received: 01/17/14 01:00

Analyte	Result Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND	1.0		ug/L			01/21/14 02:51	1
1,1,2,2-Tetrachloroethane	ND	1.0		ug/L			01/21/14 02:51	1
1,1,2-Trichloroethane	ND	1.0		ug/L			01/21/14 02:51	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND	1.0		ug/L			01/21/14 02:51	1
1,1-Dichloroethane	ND	1.0		ug/L			01/21/14 02:51	1
1,1-Dichloroethene	ND	1.0		ug/L			01/21/14 02:51	1
1,2,4-Trichlorobenzene	ND	1.0		ug/L			01/21/14 02:51	1
1,2-Dibromo-3-Chloropropane	ND	1.0		ug/L			01/21/14 02:51	1
1,2-Dichlorobenzene	ND	1.0		ug/L			01/21/14 02:51	1
1,2-Dichloroethane	ND	1.0		ug/L			01/21/14 02:51	1
1,2-Dichloropropane	ND	1.0		ug/L			01/21/14 02:51	1
1,3-Dichlorobenzene	ND	1.0		ug/L			01/21/14 02:51	1
1,4-Dichlorobenzene	ND	1.0		ug/L			01/21/14 02:51	1
2-Butanone (MEK)	ND	10		ug/L			01/21/14 02:51	1
2-Hexanone	ND *	5.0		ug/L			01/21/14 02:51	1
4-Methyl-2-pentanone (MIBK)	ND	5.0		ug/L			01/21/14 02:51	1
Acetone	ND	10		ug/L			01/21/14 02:51	1
Benzene	ND	1.0		ug/L			01/21/14 02:51	1
Bromodichloromethane	ND	1.0		ug/L			01/21/14 02:51	1
Bromoform	ND	1.0		ug/L			01/21/14 02:51	1
Bromomethane	ND	1.0		ug/L			01/21/14 02:51	1
Carbon disulfide	ND	1.0		ug/L			01/21/14 02:51	1
Carbon tetrachloride	ND	1.0		ug/L			01/21/14 02:51	1
Chlorobenzene	ND	1.0		ug/L			01/21/14 02:51	1
Dibromochloromethane	ND	1.0		ug/L			01/21/14 02:51	1
Chloroethane	ND	1.0		ug/L			01/21/14 02:51	1
Chloroform	ND	1.0		ug/L			01/21/14 02:51	1
Chloromethane	ND	1.0		ug/L			01/21/14 02:51	1
cis-1,2-Dichloroethene	ND	1.0		ug/L			01/21/14 02:51	1
cis-1,3-Dichloropropene	ND	1.0		ug/L			01/21/14 02:51	1

TestAmerica Buffalo

Client: CHA Inc

Acetone

Benzene

Bromoform

Bromodichloromethane

Project/Site: Solvents and Petroleum

Lab Sample ID: 480-53428-5

TestAmerica Job ID: 480-53428-1

Matrix: Water

Date Collected: 01/16/14 15:30 Date Received: 01/17/14 01:00

Method: 8260C - Volatile Organic Compounds by GC/MS

**Client Sample ID: TW-3** 

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Cyclohexane	ND		1.0		ug/L			01/21/14 02:51	1
Dichlorodifluoromethane	ND		1.0		ug/L			01/21/14 02:51	1
Ethylbenzene	ND		1.0		ug/L			01/21/14 02:51	1
1,2-Dibromoethane	ND		1.0		ug/L			01/21/14 02:51	1
Isopropylbenzene	ND		1.0		ug/L			01/21/14 02:51	1
Methyl acetate	ND		1.0		ug/L			01/21/14 02:51	1
Methyl tert-butyl ether	ND		1.0		ug/L			01/21/14 02:51	1
Methylcyclohexane	ND		1.0		ug/L			01/21/14 02:51	1
Methylene Chloride	ND		1.0		ug/L			01/21/14 02:51	1
Styrene	ND		1.0		ug/L			01/21/14 02:51	1
Tetrachloroethene	ND		1.0		ug/L			01/21/14 02:51	1
Toluene	ND		1.0		ug/L			01/21/14 02:51	1
trans-1,2-Dichloroethene	ND		1.0		ug/L			01/21/14 02:51	1
trans-1,3-Dichloropropene	ND		1.0		ug/L			01/21/14 02:51	1
Trichloroethene	ND		1.0		ug/L			01/21/14 02:51	1
Trichlorofluoromethane	ND		1.0		ug/L			01/21/14 02:51	1
Vinyl chloride	ND		1.0		ug/L			01/21/14 02:51	1
Xylenes, Total	ND		2.0		ug/L			01/21/14 02:51	1
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	94		71 - 126					01/21/14 02:51	1
1,2-Dichloroethane-d4 (Surr)	93		66 - 137					01/21/14 02:51	1
4-Bromofluorobenzene (Surr)	115		73 - 120					01/21/14 02:51	1

Client Sample ID: TW-4 Lab Sample ID: 480-53428-6

Date Collected: 01/16/14 15:50 Matrix: Water
Date Received: 01/17/14 01:00

Analyte	Result C	Qualifier	RL MI	DL Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		1.0	ug/L			01/21/14 03:16	1
1,1,2,2-Tetrachloroethane	ND		1.0	ug/L			01/21/14 03:16	1
1,1,2-Trichloroethane	ND		1.0	ug/L			01/21/14 03:16	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		1.0	ug/L			01/21/14 03:16	1
1,1-Dichloroethane	ND		1.0	ug/L			01/21/14 03:16	1
1,1-Dichloroethene	ND		1.0	ug/L			01/21/14 03:16	1
1,2,4-Trichlorobenzene	ND		1.0	ug/L			01/21/14 03:16	1
1,2-Dibromo-3-Chloropropane	ND		1.0	ug/L			01/21/14 03:16	1
1,2-Dichlorobenzene	ND		1.0	ug/L			01/21/14 03:16	1
1,2-Dichloroethane	ND		1.0	ug/L			01/21/14 03:16	1
1,2-Dichloropropane	ND		1.0	ug/L			01/21/14 03:16	1
1,3-Dichlorobenzene	ND		1.0	ug/L			01/21/14 03:16	1
1,4-Dichlorobenzene	ND		1.0	ug/L			01/21/14 03:16	1
2-Butanone (MEK)	ND		10	ug/L			01/21/14 03:16	1
2-Hexanone	ND *	•	5.0	ug/L			01/21/14 03:16	1
4-Methyl-2-pentanone (MIBK)	ND		5.0	ug/L			01/21/14 03:16	1

TestAmerica Buffalo

01/21/14 03:16

01/21/14 03:16

01/21/14 03:16

01/21/14 03:16

10

1.0

1.0

1.0

ug/L

ug/L

ug/L

ug/L

ND

ND

ND

ND

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-1

Lab Sample ID: 480-53428-6

Matrix: Water

Client Sample ID: TW-4

Date Collected: 01/16/14 15:50 Date Received: 01/17/14 01:00

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bromomethane	ND		1.0		ug/L			01/21/14 03:16	1
Carbon disulfide	ND		1.0		ug/L			01/21/14 03:16	1
Carbon tetrachloride	ND		1.0		ug/L			01/21/14 03:16	1
Chlorobenzene	ND		1.0		ug/L			01/21/14 03:16	1
Dibromochloromethane	ND		1.0		ug/L			01/21/14 03:16	1
Chloroethane	ND		1.0		ug/L			01/21/14 03:16	1
Chloroform	ND		1.0		ug/L			01/21/14 03:16	1
Chloromethane	ND		1.0		ug/L			01/21/14 03:16	1
cis-1,2-Dichloroethene	ND		1.0		ug/L			01/21/14 03:16	1
cis-1,3-Dichloropropene	ND		1.0		ug/L			01/21/14 03:16	1
Cyclohexane	ND		1.0		ug/L			01/21/14 03:16	1
Dichlorodifluoromethane	ND		1.0		ug/L			01/21/14 03:16	1
Ethylbenzene	ND		1.0		ug/L			01/21/14 03:16	1
1,2-Dibromoethane	ND		1.0		ug/L			01/21/14 03:16	1
Isopropylbenzene	ND		1.0		ug/L			01/21/14 03:16	1
Methyl acetate	ND		1.0		ug/L			01/21/14 03:16	1
Methyl tert-butyl ether	ND		1.0		ug/L			01/21/14 03:16	1
Methylcyclohexane	ND		1.0		ug/L			01/21/14 03:16	1
Methylene Chloride	ND		1.0		ug/L			01/21/14 03:16	1
Styrene	ND		1.0		ug/L			01/21/14 03:16	1
Tetrachloroethene	ND		1.0		ug/L			01/21/14 03:16	1
Toluene	ND		1.0		ug/L			01/21/14 03:16	1
trans-1,2-Dichloroethene	ND		1.0		ug/L			01/21/14 03:16	1
trans-1,3-Dichloropropene	ND		1.0		ug/L			01/21/14 03:16	1
Trichloroethene	ND		1.0		ug/L			01/21/14 03:16	1
Trichlorofluoromethane	ND		1.0		ug/L			01/21/14 03:16	1
Vinyl chloride	ND		1.0		ug/L			01/21/14 03:16	1
Xylenes, Total	ND		2.0		ug/L			01/21/14 03:16	1
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	94		71 - 126			-		01/21/14 03:16	1
1,2-Dichloroethane-d4 (Surr)	91		66 - 137					01/21/14 03:16	1
4-Bromofluorobenzene (Surr)	113		73 - 120					01/21/14 03:16	1

**Client Sample ID: Trip Blank** 

Date Collected: 01/16/14 00:00

Date Received: 01/17/14 01:00

Lab Sample ID: 480-53428-11

Matrix: Water

Analyte	Result Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1,2-Tetrachloroethane	ND	1.0		ug/L			01/21/14 01:34	1
1,1,1-Trichloroethane	ND	1.0		ug/L			01/21/14 01:34	1
1,1,2,2-Tetrachloroethane	ND	1.0		ug/L			01/21/14 01:34	1
1,1,2-Trichloroethane	ND	1.0		ug/L			01/21/14 01:34	1
1,1-Dichloroethane	ND	1.0		ug/L			01/21/14 01:34	1
1,1-Dichloroethene	ND	1.0		ug/L			01/21/14 01:34	1
1,2,4-Trichlorobenzene	ND	1.0		ug/L			01/21/14 01:34	1
1,1-Dichloropropene	ND	1.0		ug/L			01/21/14 01:34	1
1,2-Dibromo-3-Chloropropane	ND	1.0		ug/L			01/21/14 01:34	1
1,2,3-Trichlorobenzene	ND	1.0		ug/L			01/21/14 01:34	1

TestAmerica Buffalo

FOIL199427 1/27/2014

Client: CHA Inc TestAmerica Job ID: 480-53428-1

Project/Site: Solvents and Petroleum

**Client Sample ID: Trip Blank** 

Lab Sample ID: 480-53428-11

Date Collected: 01/16/14 00:00 Matrix: Water Date Received: 01/17/14 01:00

Analyte	Result	Qualifier RL	MDL	Unit	D	Prepared	Analyzed	Dil Fa
1,2-Dibromoethane	ND	1.0		ug/L			01/21/14 01:34	
1,2,3-Trichloropropane	ND	1.0		ug/L			01/21/14 01:34	
1,2-Dichlorobenzene	ND	1.0		ug/L			01/21/14 01:34	
1,2-Dichloroethane	ND	1.0		ug/L			01/21/14 01:34	
1,2-Dichloropropane	ND	1.0		ug/L			01/21/14 01:34	
1,2,4-Trimethylbenzene	ND	1.0		ug/L			01/21/14 01:34	
1,3-Dichlorobenzene	ND	1.0		ug/L			01/21/14 01:34	
1,4-Dichlorobenzene	ND	1.0		ug/L			01/21/14 01:34	
Benzene	ND	1.0		ug/L			01/21/14 01:34	
1,3,5-Trimethylbenzene	ND	1.0		ug/L			01/21/14 01:34	
Bromodichloromethane	ND	1.0		ug/L			01/21/14 01:34	
Bromoform	ND	1.0		ug/L			01/21/14 01:34	
1,3-Dichloropropane	ND	1.0		ug/L			01/21/14 01:34	
Bromomethane	ND	1.0		ug/L			01/21/14 01:34	
Carbon tetrachloride	ND	1.0		ug/L			01/21/14 01:34	
Chlorobenzene	ND	1.0		ug/L			01/21/14 01:34	
2,2-Dichloropropane	ND	1.0		ug/L			01/21/14 01:34	
Dibromochloromethane	ND	1.0		ug/L			01/21/14 01:34	
Chloroethane	ND	1.0		ug/L			01/21/14 01:34	
Chloroform	ND	1.0		ug/L			01/21/14 01:34	
2-Chlorotoluene	ND	1.0		ug/L			01/21/14 01:34	
Chloromethane	ND	1.0		ug/L			01/21/14 01:34	
cis-1,2-Dichloroethene	ND	1.0		ug/L			01/21/14 01:34	
cis-1,3-Dichloropropene	ND	1.0		ug/L			01/21/14 01:34	
Dichlorodifluoromethane	ND	1.0		ug/L			01/21/14 01:34	
4-Chlorotoluene	ND	1.0		ug/L			01/21/14 01:34	
Ethylbenzene	ND	1.0		ug/L			01/21/14 01:34	
4-Isopropyltoluene	ND	1.0		ug/L			01/21/14 01:34	
Isopropylbenzene	ND	1.0		ug/L			01/21/14 01:34	
Methylene Chloride	ND	1.0		ug/L			01/21/14 01:34	
Styrene	ND	1.0		ug/L			01/21/14 01:34	
Bromobenzene	ND	1.0		ug/L			01/21/14 01:34	
Tetrachloroethene	ND	1.0		ug/L			01/21/14 01:34	
Toluene	ND	1.0		ug/L			01/21/14 01:34	
trans-1,2-Dichloroethene	ND	1.0		ug/L			01/21/14 01:34	
trans-1,3-Dichloropropene	ND	1.0		ug/L			01/21/14 01:34	
Trichloroethene	ND	1.0		ug/L			01/21/14 01:34	
Trichlorofluoromethane	ND	1.0		ug/L			01/21/14 01:34	
Bromochloromethane	ND	1.0		ug/L			01/21/14 01:34	
Vinyl chloride	ND	1.0		ug/L			01/21/14 01:34	
Dibromomethane	ND	1.0		ug/L			01/21/14 01:34	
Hexachlorobutadiene	ND	1.0		ug/L			01/21/14 01:34	
m,p-Xylene	ND	2.0					01/21/14 01:34	
Maphthalene	ND ND	1.0		ug/L			01/21/14 01:34	
				ug/L			01/21/14 01:34	
n-Butylbenzene N-Propylbenzene	ND	1.0		ug/L				
• •	ND	1.0		ug/L			01/21/14 01:34	
o-Xylene	ND	1.0		ug/L			01/21/14 01:34	
sec-Butylbenzene tert-Butylbenzene	ND ND	1.0 1.0		ug/L ug/L			01/21/14 01:34 01/21/14 01:34	

TestAmerica Buffalo

Client: CHA Inc TestAmerica Job ID: 480-53428-1

Project/Site: Solvents and Petroleum

Client Sample ID: Trip Blank

Lab Sample ID: 480-53428-11

Date Collected: 01/16/14 00:00 Matrix: Water

Date Received: 01/17/14 01:00

Surrogate	%Recovery Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	71	66 - 137		01/21/14 01:34	1
Toluene-d8 (Surr)	73	71 - 126		01/21/14 01:34	1
4-Bromofluorobenzene (Surr)	87	73 - 120		01/21/14 01:34	1

<u>۾</u>

9

11

13

14

1

## **Surrogate Summary**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-1

Method: 8260C - Volatile Organic Compounds by GC/MS

Matrix: Water Prep Type: Total/NA

				Percent Surro	gate Recovery (Acceptance Limits)
		12DCE	TOL	BFB	
Lab Sample ID	Client Sample ID	(66-137)	(71-126)	(73-120)	
480-53428-3	TW-1	95	96	113	
480-53428-4	TW-2	95	96	114	
480-53428-5	TW-3	93	94	115	
480-53428-6	TW-4	91	94	113	
480-53428-11	Trip Blank	71	73	87	
LCS 480-162441/4	Lab Control Sample	99	97	116	
MB 480-162441/6	Method Blank	91	95	115	

12DCE = 1,2-Dichloroethane-d4 (Surr)

TOL = Toluene-d8 (Surr)

BFB = 4-Bromofluorobenzene (Surr)

## **QC Sample Results**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-1

## Method: 8260C - Volatile Organic Compounds by GC/MS

Lab Sample ID: MB 480-162441/6

**Matrix: Water** 

Client Sample ID: Method Blank **Prep Type: Total/NA** 

Analysis Batch: 162441						
	MB MB		MB1 11 11			D.: E
Analyte	Result Qualifier	RL	MDL Unit	D Prepared	Analyzed	Dil Fac
1,1,1,2-Tetrachloroethane	ND ND	1.0	ug/L		01/21/14 00:29	1
1,1,1-Trichloroethane		1.0	ug/L		01/21/14 00:29	1
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L		01/21/14 00:29	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND	1.0	ug/L		01/21/14 00:29	1
1,1,2-Trichloroethane	ND	1.0	ug/L		01/21/14 00:29	1
1,1-Dichloroethane	ND	1.0	ug/L		01/21/14 00:29	1
1,1-Dichloroethene	ND	1.0	ug/L		01/21/14 00:29	1
1,2,4-Trichlorobenzene	ND	1.0	ug/L		01/21/14 00:29	1
1,1-Dichloropropene	ND	1.0	ug/L		01/21/14 00:29	1
1,2-Dibromo-3-Chloropropane	ND	1.0	ug/L		01/21/14 00:29	1
1,2,3-Trichlorobenzene	ND	1.0	ug/L		01/21/14 00:29	1
1,2,3-Trichloropropane	ND	1.0	ug/L		01/21/14 00:29	1
1,2-Dichlorobenzene	ND	1.0	ug/L		01/21/14 00:29	1
1,2-Dichloroethane	ND	1.0	ug/L		01/21/14 00:29	1
2-Butanone (MEK)	ND	10	ug/L		01/21/14 00:29	1
1,2-Dichloropropane	ND	1.0	ug/L		01/21/14 00:29	1
2-Hexanone	ND	5.0	ug/L		01/21/14 00:29	1
1,2,4-Trimethylbenzene	ND	1.0	ug/L		01/21/14 00:29	1
4-Methyl-2-pentanone (MIBK)	ND	5.0	ug/L		01/21/14 00:29	1
1,3-Dichlorobenzene	ND	1.0	ug/L		01/21/14 00:29	1
Acetone	ND	10	ug/L		01/21/14 00:29	1
1,4-Dichlorobenzene	ND	1.0	ug/L		01/21/14 00:29	1
Benzene	ND	1.0	ug/L		01/21/14 00:29	1
1,3,5-Trimethylbenzene	ND	1.0	ug/L		01/21/14 00:29	1
Bromodichloromethane	ND	1.0	ug/L		01/21/14 00:29	1
Bromoform	ND	1.0	ug/L		01/21/14 00:29	1
Carbon disulfide	ND	1.0	ug/L		01/21/14 00:29	1
1,3-Dichloropropane	ND	1.0	ug/L		01/21/14 00:29	1
Bromomethane	ND	1.0	ug/L		01/21/14 00:29	1
Carbon tetrachloride	ND	1.0	ug/L		01/21/14 00:29	1
Chlorobenzene	ND	1.0	ug/L		01/21/14 00:29	1
2,2-Dichloropropane	ND	1.0	ug/L		01/21/14 00:29	1
Dibromochloromethane	ND	1.0	ug/L		01/21/14 00:29	1
Chloroethane	ND	1.0	ug/L		01/21/14 00:29	1
Chloroform	ND	1.0	ug/L		01/21/14 00:29	1
2-Chlorotoluene	ND	1.0	ug/L		01/21/14 00:29	1
Cyclohexane	ND	1.0	ug/L		01/21/14 00:29	1
Chloromethane	ND	1.0	ug/L		01/21/14 00:29	1
cis-1,2-Dichloroethene	ND	1.0	ug/L		01/21/14 00:29	1
1,2-Dibromoethane	ND	1.0	ug/L		01/21/14 00:29	1
cis-1,3-Dichloropropene	ND	1.0	ug/L		01/21/14 00:29	1
Dichlorodifluoromethane	ND	1.0	ug/L		01/21/14 00:29	1
4-Chlorotoluene	ND	1.0	ug/L		01/21/14 00:29	1
Methyl acetate	ND	1.0	ug/L		01/21/14 00:29	1
Ethylbenzene	ND	1.0	ug/L		01/21/14 00:29	1
Methyl tert-butyl ether	ND	1.0	ug/L		01/21/14 00:29	1
4-Isopropyltoluene	ND	1.0	ug/L		01/21/14 00:29	1
Methylcyclohexane	ND	1.0	ug/L		01/21/14 00:29	1

TestAmerica Buffalo

## **QC Sample Results**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-1

#### Method: 8260C - Volatile Organic Compounds by GC/MS (Continued)

MB MB

Lab Sample ID: MB 480-162441/6

**Matrix: Water** 

Analysis Batch: 162441

Client Sample ID: Method Blank

Prep Type: Total/NA

	IVID	IVID							
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fa
Isopropylbenzene	ND		1.0		ug/L			01/21/14 00:29	
Methylene Chloride	ND		1.0		ug/L			01/21/14 00:29	
Styrene	ND		1.0		ug/L			01/21/14 00:29	
Bromobenzene	ND		1.0		ug/L			01/21/14 00:29	
Tetrachloroethene	ND		1.0		ug/L			01/21/14 00:29	
Toluene	ND		1.0		ug/L			01/21/14 00:29	
trans-1,2-Dichloroethene	ND		1.0		ug/L			01/21/14 00:29	•
trans-1,3-Dichloropropene	ND		1.0		ug/L			01/21/14 00:29	
Trichloroethene	ND		1.0		ug/L			01/21/14 00:29	
Trichlorofluoromethane	ND		1.0		ug/L			01/21/14 00:29	
Bromochloromethane	ND		1.0		ug/L			01/21/14 00:29	
Xylenes, Total	ND		2.0		ug/L			01/21/14 00:29	
Vinyl chloride	ND		1.0		ug/L			01/21/14 00:29	
Dibromomethane	ND		1.0		ug/L			01/21/14 00:29	
Hexachlorobutadiene	ND		1.0		ug/L			01/21/14 00:29	
m,p-Xylene	ND		2.0		ug/L			01/21/14 00:29	
Naphthalene	ND		1.0		ug/L			01/21/14 00:29	
n-Butylbenzene	ND		1.0		ug/L			01/21/14 00:29	
N-Propylbenzene	ND		1.0		ug/L			01/21/14 00:29	
o-Xylene	ND		1.0		ug/L			01/21/14 00:29	
sec-Butylbenzene	ND		1.0		ug/L			01/21/14 00:29	
tert-Butylbenzene	ND		1.0		ug/L			01/21/14 00:29	

МВ	MB	

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	91		66 - 137		01/21/14 00:29	1
Toluene-d8 (Surr)	95		71 - 126		01/21/14 00:29	1
4-Bromofluorobenzene (Surr)	115		73 - 120		01/21/14 00:29	1

Lab Sample ID: LCS 480-162441/4

**Matrix: Water** 

Analysis Batch: 162441

	Spike	LCS	LCS				%Rec.	
Analyte	Added	Result	Qualifier	Unit	D	%Rec	Limits	
1,1-Dichloroethane	25.0	25.2		ug/L		101	71 - 129	
1,1-Dichloroethene	25.0	26.4		ug/L		106	58 - 121	
1,2-Dichlorobenzene	25.0	22.7		ug/L		91	80 - 124	
1,2-Dichloroethane	25.0	24.1		ug/L		96	75 <sub>-</sub> 127	
1,2,4-Trimethylbenzene	25.0	21.7		ug/L		87	76 - 121	
Benzene	25.0	25.6		ug/L		102	71 - 124	
Chlorobenzene	25.0	24.9		ug/L		100	72 - 120	
cis-1,2-Dichloroethene	25.0	26.0		ug/L		104	74 - 124	
Ethylbenzene	25.0	24.1		ug/L		96	77 - 123	
Methyl tert-butyl ether	25.0	26.0		ug/L		104	64 - 127	
Tetrachloroethene	25.0	28.5		ug/L		114	74 - 122	
Toluene	25.0	24.6		ug/L		98	80 - 122	
trans-1,2-Dichloroethene	25.0	26.1		ug/L		104	73 - 127	
Trichloroethene	25.0	26.2		ug/L		105	74 - 123	
m,p-Xylene	25.0	25.1		ug/L		100	76 - 122	

TestAmerica Buffalo

FOIL199432 1/27/2014

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Page 15 of 23

## **QC Sample Results**

Client: CHA Inc TestAmerica Job ID: 480-53428-1

Project/Site: Solvents and Petroleum

Lab Sample ID: LCS 480-162441/4

**Matrix: Water** 

Analysis Batch: 162441

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

LCS LCS Spike %Rec. Analyte Added Result Qualifier Unit %Rec Limits o-Xylene 25.0 24.9 100 76 - 122 ug/L

	LCS	LCS	
Surrogate	%Recovery	Qualifier	Limits
1,2-Dichloroethane-d4 (Surr)	99		66 - 137
Toluene-d8 (Surr)	97		71 - 126
4-Bromofluorobenzene (Surr)	116		73 - 120

Method: 8260C - Volatile Organic Compounds by GC/MS (Continued)

## **QC Association Summary**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-1

#### **GC/MS VOA**

#### Analysis Batch: 162441

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
480-53428-3	TW-1	Total/NA	Water	8260C	
480-53428-4	TW-2	Total/NA	Water	8260C	
480-53428-5	TW-3	Total/NA	Water	8260C	
480-53428-6	TW-4	Total/NA	Water	8260C	
480-53428-11	Trip Blank	Total/NA	Water	8260C	
LCS 480-162441/4	Lab Control Sample	Total/NA	Water	8260C	
MB 480-162441/6	Method Blank	Total/NA	Water	8260C	

3

4

5

6

8

9

10

12

10

15

### Lab Chronicle

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-1

Lab Sample ID: 480-53428-3

10

Matrix: Water

**Matrix: Water** 

**Matrix: Water** 

Matrix: Water

Date Collected: 01/16/14 13:20 Date Received: 01/17/14 01:00

Client Sample ID: TW-1

Batch Dilution Batch Batch Prepared Prep Type Type Method Run Factor Number or Analyzed Analyst Lab Total/NA Analysis 8260C 162441 01/21/14 02:00 LCH TAL BUF

Client Sample ID: TW-2 Lab Sample ID: 480-53428-4

Date Collected: 01/16/14 14:00 Matrix: Water

Date Received: 01/17/14 01:00

Batch Batch Dilution Batch Prepared Method Factor Туре Run Number or Analyzed Prep Type Analyst Lab Total/NA 8260C 162441 TAL BUF Analysis 01/21/14 02:25 LCH

**Client Sample ID: TW-3** Lab Sample ID: 480-53428-5

Date Collected: 01/16/14 15:30

Date Received: 01/17/14 01:00

Batch Batch Dilution Batch Prepared Prep Type Туре Method Run Factor Number or Analyzed Analyst Lab Total/NA Analysis 8260C 162441 01/21/14 02:51 LCH TAL BUF

Client Sample ID: TW-4 Lab Sample ID: 480-53428-6

Date Collected: 01/16/14 15:50

Date Received: 01/17/14 01:00

Batch Batch Dilution Batch Prepared Method Prep Type Туре Run Factor Number or Analyzed Analyst Lab Total/NA Analysis 8260C 162441 01/21/14 03:16 LCH TAL BUF

Lab Sample ID: 480-53428-11 Client Sample ID: Trip Blank

Date Collected: 01/16/14 00:00

Date Received: 01/17/14 01:00

	Batch	Batch		Dilution	Batch	Prepared		
Prep Type	Туре	Method	Run	Factor	Number	or Analyzed	Analyst	Lab
Total/NA	Analysis	8260C			162441	01/21/14 01:34	LCH	TAL BUF

**Laboratory References:** 

TAL BUF = TestAmerica Buffalo, 10 Hazelwood Drive, Amherst, NY 14228-2298, TEL (716)691-2600

# **Certification Summary**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-1

### **Laboratory: TestAmerica Buffalo**

The certifications listed below are applicable to this report.

Authority	Program	EPA Region	Certification ID	<b>Expiration Date</b>
New York	NELAP	2	10026	03-31-14

5

- 5

4

Ω

9

11

40

14

# **Method Summary**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-1

Method	Method Description	Protocol	Laboratory
8260C	Volatile Organic Compounds by GC/MS	SW846	TAL BUF

### **Protocol References:**

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

### Laboratory References:

TAL BUF = TestAmerica Buffalo, 10 Hazelwood Drive, Amherst, NY 14228-2298, TEL (716)691-2600

5

4

5

8

10

11

40

14

# **Sample Summary**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
480-53428-3	TW-1	Water	01/16/14 13:20	01/17/14 01:00
480-53428-4	TW-2	Water	01/16/14 14:00	01/17/14 01:00
480-53428-5	TW-3	Water	01/16/14 15:30	01/17/14 01:00
480-53428-6	TW-4	Water	01/16/14 15:50	01/17/14 01:00
480-53428-11	Trip Blank	Water	01/16/14 00:00	01/17/14 01:00

3

4

6

8

9

1 1

12

14



# Chain of Custody Record

Table   Sample   Sa		Sampler: Menn CK	Gilbert	Lab PM Gray-E	Lab PM: Gray-Erdmann, Peggy	, Pegg	7		$\overline{}$	Carrier Tra	Carrier Tracking No(s):	<u></u>	COC No: 480-43507-11762.1	762.1
Annalysis Requested  The Requested (anys)  Somple Date  Time Of Checkers  Time Of Checkers  Somple Date  Time Of Checkers  Time Of Checkers  Somple Date  Time Of Checkers  Ti		l	7331	E-Mail: peggy	gray-erc	dmann	@testam	ericaino	moo:				Page: Page 1 of 1	
Note   Companies							Ā	nalysi	s Red	uestec	_		.# qor	
Sample Date  Sampl		Due Date Requested:								_			Preservation (	
Sample Date  Sample Concord  Sample Date  Sa		ı						CI_E		(45	101		B - NaOH C - Zn Acetate	
Sample Date   Sample   Sampl			and and					009ÞW		-	de		D - Nitric Acid E - NaHSO4	
Sample Date   Sample   Sampl		PO#: 8423.2010.44000	>		10			S ,əls		12	bin		G - Amchlor H - Ascorbic Aci	
		WO #:			POSTANCHANIE	nodr		etrate		OB	<del>/</del> +			
Sample Date   Time   Gagrab    Time		Project #: 48004389			10 S9					00	101			vv - pn 4-5 Z - other (specify)
Sample Date   Time   Gracion   Time   Gracion   Time   Gracion   Time   Gracion   Time   Gracion   Time   Time   Gracion   Time   Tim		SSOW#:			r) as					78	- 8			
					Pertorm MS/M					5 570N	31018			Instructions/Note:
		/ \		ion Code:	\frac{1}{\times}	4	A CB	_	_					
11/2   14   152.2   C   Water   X   X   X   X   X   X   X   X   X			4	Water	_	7	×	×	X		×			_
			22 6	Water	^	-	×	X			- X			
140°   5   140°   140°				Water						×			3	2
1550 C   Wilth		1 140	9	wholes									1	15
1550 C   With C		163	6	Water						×			J. G.W.	anops
1145   Sample Disposal (A fee may be assessed if samples are retained longer than 1 mo   1525   Sample Disposal (A fee may be assessed if samples are retained longer than 1 mo   1525   Sample Disposal (A fee may be assessed if samples are retained longer than 1 mo   Received by:   Sample Disposal By Lab   Archive For   Special Instructions/QC Requirements:   Spe		155	3	whi						<b>X</b>				specific RL
1145   1400   1500		930	ف	1.08	au.					<b>×</b>			2	7
1400 (		1145		118						×			7	
Sample Disposal (A fee may be assessed if samples are retained longer than 1 mo   Special Instructions/QC Requirements:   Date:   Special Instructions/QC Requirements:   Method of Shipment:   Special Instructions/QC Requirements:   Method of Shipment:   Company   Received by:   Coder Temperature(s)*C and Other Remarks:   ST SSF   Coder Temperature(s)*C and Other Remarks:   SSF   Coder Temperature(s)*C and Other Remarks:   ST SSF   Coder Temperature(s		140		Soil									7	
Sample Disposal (A fee may be assessed if samples are retained longer than 1 mo   Poison B		7 152	1	1.8						×	yet's		2	
Special Instructions/QC Requirements:    Date:   Date:   Special Instructions/QC Requirements:   Method of Shipment:   Special Instructions/QC Requirements:   Method of Shipment:   Special Instructions/QC Requirements:   Method of Shipment:   Special Instructions/QC Requirements:   Special Instructions/QC Requirements:   Method of Shipment:   Special Instructions/QC Requirements:   Special Instructions/QC Representations/QC Repr							×							
Date:   Time:   Time:   Time:   Method of Shipment:   Company   Received by:   Confirme:			Radiological		Samp	le Disp	To Clier	fee ma	y be a	ssesse	l if samp	les are n	etained longer tha	n 1 month) Months
Date:    Date:   Time:   Received by:					Specia	al Instru	ctions/C	C Req	uiremer	ıts:				
Company Received by:  (4) 19(1) Company Received by:  Company Received by:  Cooler Temperature(s) °C and Other Remarks:  Cooler Temperature(s) °C and Other	•	Date:			ime:					Meti	od of Ship	ment:		
Company Received by:  Company Received by:  Cooler Temperature(s) °C and Other Remarks:  Cooler Temperature(s)	11/		1	Company	Re	a series	17	17.77		$\cdot$	Date	14-/	4.17.00	> Copped C
Cooler Temperature(s) °C and Other Remarks: 37 25 74 C		14. 1	3	Company	- Re	e e e e e e e e e e e e e e e e e e e		3	1		Date	. ( 7 . /		Company
37 35		Date/Time:	1.83	Sompany	Re	ceived by	2				Date	a∕Time:		Company
					පි	oler Tem	perature(s	°C and	Other Rei	narks:	7	7		4

FOIL199439 1/27/2014

# **Login Sample Receipt Checklist**

Client: CHA Inc Job Number: 480-53428-1

Login Number: 53428 List Source: TestAmerica Buffalo

List Number: 1

Creator: Wienke, Robert K

Creator: Wienke, Robert K		
Question	Answer	Comment
Radioactivity either was not measured or, if measured, is at or below background	True	
The cooler's custody seal, if present, is intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the sample IDs on the containers and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
VOA sample vials do not have headspace or bubble is <6mm (1/4") in diameter.	True	
If necessary, staff have been informed of any short hold time or quick TAT needs	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Sampling Company provided.	True	CHA
Samples received within 48 hours of sampling.	True	
Samples requiring field filtration have been filtered in the field.	N/A	
Chlorine Residual checked.	N/A	



THE LEADER IN ENVIRONMENTAL TESTING

# ANALYTICAL REPORT

TestAmerica Laboratories, Inc.

TestAmerica Buffalo 10 Hazelwood Drive Amherst, NY 14228-2298 Tel: (716)691-2600


TestAmerica Job ID: 480-53428-2

Client Project/Site: Solvents and Petroleum

For:

CHA Inc 441 South Salina Street Syracuse, New York 13202

Attn: Katie E Flood



Authorized for release by: 1/24/2014 12:25:41 PM

Peggy Gray-Erdmann, Client Relations Manager (716)504-9829

peggy.gray-erdmann@testamericainc.com

·····LINKS ·······

Review your project results through

Total Access

**Have a Question?** 



Visit us at: www.testamericainc.com

The test results in this report meet all 2003 NELAC and 2009 TNI requirements for accredited parameters, exceptions are noted in this report. This report may not be reproduced except in full, and with written approval from the laboratory. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory. FOIL199441

# **Table of Contents**

Cover Page	1
Table of Contents	2
Definitions/Glossary	3
Case Narrative	4
Detection Summary	5
Client Sample Results	6
Surrogate Summary	11
QC Sample Results	12
QC Association Summary	14
Lab Chronicle	15
Certification Summary	16
Method Summary	17
Sample Summary	18
Chain of Custody	19
Receipt Checklists	20

10

12

13

# **Definitions/Glossary**

Client: CHA Inc

Project/Site: Solvents and Petroleum

Toxicity Equivalent Factor (Dioxin)

Toxicity Equivalent Quotient (Dioxin)

TestAmerica Job ID: 480-53428-2

# Glossary

TEF

TEQ

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CNF	Contains no Free Liquid
DER	Duplicate error ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision level concentration
MDA	Minimum detectable activity
EDL	Estimated Detection Limit
MDC	Minimum detectable concentration
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
NC	Not Calculated
ND	Not detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RER	Relative error ratio
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points

### **Case Narrative**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-2

Job ID: 480-53428-2

Laboratory: TestAmerica Buffalo

Narrative

Job Narrative 480-53428-2

### Comments

No additional comments.

### Receipt

The samples were received on 1/17/2014 1:00 AM; the samples arrived in good condition, properly preserved and, where required, on ice. The temperatures of the 2 coolers at receipt time were 3.5° C and 3.7° C.

### Except:

The following sample was submitted for analysis; however, it was not listed on the Chain-of-Custody (COC): MW-1R (480-53428-12). Logged in as per volume received.

### GC/MS VOA

Method(s) 8260C: Reported analyte concentrations in the following sample(s) are below 200ug/kg and may be biased low due to the sample(s) not being collected according to 5035-L/5035A-L low-level specifications: TW-1 (480-53428-7), TW-2 (480-53428-8), TW-3 (480-53428-9), TW-4 (480-53428-10).

Method(s) 8260C: The large number of analytes included in the continuing calibration verification (CCV) for batch 162927 gives a high probability that one or more analytes will be outside acceptance criteria. As indicated in the reference method, analysis may proceed as long as no more than 20% of the analytes are outside the method-defined %D criteria.

Method(s) 8260C: The method blank for batch 162927 contained Acetone and Methylene chloride above the method detection limit. These target analyte concentrations were less than the reporting limit (RL); therefore, re-extraction and/or re-analysis of samples was not performed.

No other analytical or quality issues were noted.

O

R

9

12

13

# **Detection Summary**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-2

Client Sample ID: TW-1						La	ıb	Sample II	D: 480-53428-7
Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Methylene Chloride	16		5.0		ug/Kg	1	₩	8260C	Total/NA
Client Sample ID: TW-2						La	ıb	Sample II	D: 480-53428-8
Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Methylene Chloride	16		5.0		ug/Kg	1	₩	8260C	Total/NA
Client Sample ID: TW-3						La	ıb	Sample II	D: 480-53428-9
Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Methylene Chloride	17		5.0		ug/Kg	1	₩	8260C	Total/NA

Client Sample ID: TW-4 Lab Sample ID: 480-53428-10

Analyte	Result	Qualifier	RL	MDL Unit	Dil Fac [	Method	Prep Type
Methylene Chloride	16		5.0	ug/Kg	1	8260C	Total/NA

Client: CHA Inc

**Client Sample ID: TW-1** 

Date Collected: 01/16/14 09:30

Date Received: 01/17/14 01:00

Project/Site: Solvents and Petroleum

Lab Sample ID: 480-53428-7

TestAmerica Job ID: 480-53428-2

Matrix: Solid

Percent Solids: 88.0

Analyte		Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		5.0		ug/Kg	#	01/23/14 10:41	01/23/14 16:03	1
1,1,2,2-Tetrachloroethane	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:03	1
1,1,2-Trichloroethane	ND		5.0		ug/Kg	*	01/23/14 10:41	01/23/14 16:03	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
1,1-Dichloroethane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
1,1-Dichloroethene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
1,2,4-Trichlorobenzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
1,2-Dibromo-3-Chloropropane	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:03	1
1,2-Dichlorobenzene	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:03	1
1,2-Dichloroethane	ND		5.0		ug/Kg	\$	01/23/14 10:41	01/23/14 16:03	1
1,2-Dichloropropane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
1,3-Dichlorobenzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
1,4-Dichlorobenzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
2-Butanone (MEK)	ND		25		ug/Kg	₩	01/23/14 10:41	01/23/14 16:03	1
2-Hexanone	ND		25		ug/Kg	₩	01/23/14 10:41	01/23/14 16:03	1
4-Methyl-2-pentanone (MIBK)	ND		25		ug/Kg		01/23/14 10:41	01/23/14 16:03	1
Acetone	ND		25		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
Benzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
Bromodichloromethane	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 16:03	1
Bromoform	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:03	1
Bromomethane	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:03	1
Carbon disulfide	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 16:03	1
Carbon tetrachloride	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
Chlorobenzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
Dibromochloromethane	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 16:03	1
Chloroethane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
Chloroform	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
Chloromethane	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 16:03	1
cis-1,2-Dichloroethene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
cis-1,3-Dichloropropene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
Cyclohexane	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 16:03	1
Dichlorodifluoromethane	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:03	1
Ethylbenzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1
1,2-Dibromoethane	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 16:03	 1
Isopropylbenzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	. 1
Methyl acetate	ND		5.0			×	01/23/14 10:41	01/23/14 16:03	1
Methyl tert-butyl ether	ND ND		5.0		ug/Kg ug/Kg		01/23/14 10:41	01/23/14 16:03	<mark>'</mark>
	ND		5.0			₩	01/23/14 10:41	01/23/14 16:03	1
Methylcyclohexane			5.0		ug/Kg	т Ф			1
Methylene Chloride	16				ug/Kg		01/23/14 10:41	01/23/14 16:03	ا 1
Styrene	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:03	1
Tetrachloroethene	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:03	1
Toluene	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 16:03	1
trans-1,2-Dichloroethene	ND		5.0		ug/Kg	Ÿ ×	01/23/14 10:41	01/23/14 16:03	1
trans-1,3-Dichloropropene	ND		5.0		ug/Kg	<b>‡</b>	01/23/14 10:41	01/23/14 16:03	1
Trichloroethene	ND		5.0		ug/Kg	<u></u>	01/23/14 10:41	01/23/14 16:03	
Trichlorofluoromethane	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 16:03	1
Vinyl chloride	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 16:03	1
Xylenes, Total	ND		10		ug/Kg	₽	01/23/14 10:41	01/23/14 16:03	1

Client: CHA Inc

Analyte

1,1,1-Trichloroethane

1,3-Dichlorobenzene

1,4-Dichlorobenzene

Bromomethane

Carbon disulfide

Project/Site: Solvents and Petroleum

Client Sample ID: TW-1

Lab Sample ID: 480-53428-7

TestAmerica Job ID: 480-53428-2

Date Collected: 01/16/14 09:30 Date Received: 01/17/14 01:00

Matrix: Solid Percent Solids: 88.0

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	99		71 - 125	01/23/14 10:41	01/23/14 16:03	1
1,2-Dichloroethane-d4 (Surr)	100		64 - 126	01/23/14 10:41	01/23/14 16:03	1
4-Bromofluorobenzene (Surr)	104		72 - 126	01/23/14 10:41	01/23/14 16:03	1

Client Sample ID: TW-2 Lab Sample ID: 480-53428-8

RL

5.0

MDL Unit

ug/Kg

ug/Kg

ug/Kg

ug/Kg

ug/Kg

D

₩

#

ψ

Prepared

01/23/14 10:41

01/23/14 10:41

01/23/14 10:41

01/23/14 10:41

01/23/14 10:41

Date Collected: 01/16/14 11:45

Method: 8260C - Volatile Organic Compounds by GC/MS

Matrix: Solid Percent Solids: 84.1

Analyzed

01/23/14 16:29

01/23/14 16:29

01/23/14 16:29

01/23/14 16:29

01/23/14 16:29

Date Received: 01/17/14 01:00

Result Qualifier

ND

ND

ND

ND

ND

Dil Fac

ND 5.0 01/23/14 10:41 01/23/14 16:29 1.1.2.2-Tetrachloroethane ug/Kg ₩ 1,1,2-Trichloroethane ND 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29 ND 5.0 1,1,2-Trichloro-1,2,2-trifluoroethane ug/Kg 01/23/14 10:41 01/23/14 16:29 1,1-Dichloroethane ND 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29 ND ug/Kg 1.1-Dichloroethene 5.0 01/23/14 10:41 01/23/14 16:29 ġ 1,2,4-Trichlorobenzene ND 5.0 01/23/14 10:41 01/23/14 16:29 ug/Kg 1,2-Dibromo-3-Chloropropane NΠ 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29 1,2-Dichlorobenzene ND 5.0 ug/Kg ₽ 01/23/14 10:41 01/23/14 16:29 φ 01/23/14 10:41 1 2-Dichloroethane ND 5.0 ug/Kg 01/23/14 16:29 1,2-Dichloropropane ND 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29

2-Butanone (MEK) ND 25 ug/Kg 01/23/14 10:41 01/23/14 16:29 ₩ 2-Hexanone ND 25 ug/Kg 01/23/14 10:41 01/23/14 16:29 4-Methyl-2-pentanone (MIBK) ND 25 ug/Kg ₫ 01/23/14 10:41 01/23/14 16:29 ₩ Acetone ND 25 ug/Kg 01/23/14 10:41 01/23/14 16:29 Benzene ND 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29 ND 5.0 01/23/14 10:41 01/23/14 16:29 Bromodichloromethane ug/Kg ď 01/23/14 10:41 ND 5.0 ug/Kg 01/23/14 16:29

5.0

5.0

5.0

5.0

Carbon tetrachloride ND 5.0 01/23/14 10:41 01/23/14 16:29 ug/Kg ŭ Chlorobenzene ND 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29 φ Dibromochloromethane ND 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29 ₩ Chloroethane ND 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29 Chloroform ND 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29 ND Chloromethane 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29 ₽ cis-1,2-Dichloroethene ND 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29 ₩ ND cis-1,3-Dichloropropene 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29 Cyclohexane ND 01/23/14 16:29

01/23/14 10:41 5.0 ug/Kg Dichlorodifluoromethane ND 01/23/14 10:41 01/23/14 16:29 5.0 ug/Kg ND ä 01/23/14 10:41 Ethylbenzene 5.0 ug/Kg 01/23/14 16:29 1,2-Dibromoethane ND 5.0 01/23/14 10:41 01/23/14 16:29 ug/Kg Ü Isopropylbenzene ND 5.0 01/23/14 10:41 01/23/14 16:29 ug/Kg ND 01/23/14 10:41 01/23/14 16:29 Methyl acetate 5.0 ug/Kg ġ Methyl tert-butyl ether ND 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29

Methylcyclohexane ND 5.0 01/23/14 10:41 01/23/14 16:29 ug/Kg ₽ **Methylene Chloride** 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29 16 Styrene ND 5.0 ug/Kg 01/23/14 10:41 01/23/14 16:29

TestAmerica Buffalo

Client: CHA Inc

Project/Site: Solvents and Petroleum

Lab Sample ID: 480-53428-8

**Client Sample ID: TW-2** 

TestAmerica Job ID: 480-53428-2

Date Collected: 01/16/14 11:45 Date Received: 01/17/14 01:00

Matrix: Solid Percent Solids: 84.1

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Tetrachloroethene	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:29	1
Toluene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:29	1
trans-1,2-Dichloroethene	ND		5.0		ug/Kg	\$	01/23/14 10:41	01/23/14 16:29	1
trans-1,3-Dichloropropene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:29	1
Trichloroethene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:29	1
Trichlorofluoromethane	ND		5.0		ug/Kg	\$	01/23/14 10:41	01/23/14 16:29	1
Vinyl chloride	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:29	1
Xylenes, Total	ND		10		ug/Kg	₽	01/23/14 10:41	01/23/14 16:29	1
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	98		71 - 125				01/23/14 10:41	01/23/14 16:29	1
1,2-Dichloroethane-d4 (Surr)	99		64 - 126				01/23/14 10:41	01/23/14 16:29	1
4-Bromofluorobenzene (Surr)	100		72 <sub>-</sub> 126				01/23/14 10:41	01/23/14 16:29	1

Lab Sample ID: 480-53428-9

Date Collected: 01/16/14 14:00 Date Received: 01/17/14 01:00

**Client Sample ID: TW-3** 

Matrix: Solid

Percent Solids: 89.7

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:55	1
1,1,2,2-Tetrachloroethane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
1,1,2-Trichloroethane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		5.0		ug/Kg	\$	01/23/14 10:41	01/23/14 16:55	1
1,1-Dichloroethane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
1,1-Dichloroethene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
1,2,4-Trichlorobenzene	ND		5.0		ug/Kg	\$	01/23/14 10:41	01/23/14 16:55	1
1,2-Dibromo-3-Chloropropane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
1,2-Dichlorobenzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
1,2-Dichloroethane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
1,2-Dichloropropane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
1,3-Dichlorobenzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
1,4-Dichlorobenzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
2-Butanone (MEK)	ND		25		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
2-Hexanone	ND		25		ug/Kg	₩	01/23/14 10:41	01/23/14 16:55	1
4-Methyl-2-pentanone (MIBK)	ND		25		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
Acetone	ND		25		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
Benzene	ND		5.0		ug/Kg	☼	01/23/14 10:41	01/23/14 16:55	1
Bromodichloromethane	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 16:55	1
Bromoform	ND		5.0		ug/Kg	☼	01/23/14 10:41	01/23/14 16:55	1
Bromomethane	ND		5.0		ug/Kg	☼	01/23/14 10:41	01/23/14 16:55	1
Carbon disulfide	ND		5.0		ug/Kg	\$	01/23/14 10:41	01/23/14 16:55	1
Carbon tetrachloride	ND		5.0		ug/Kg	☼	01/23/14 10:41	01/23/14 16:55	1
Chlorobenzene	ND		5.0		ug/Kg	☼	01/23/14 10:41	01/23/14 16:55	1
Dibromochloromethane	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 16:55	1
Chloroethane	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:55	1
Chloroform	ND		5.0		ug/Kg	☼	01/23/14 10:41	01/23/14 16:55	1
Chloromethane	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 16:55	1
cis-1,2-Dichloroethene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
cis-1,3-Dichloropropene	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:55	1

Client: CHA Inc

Project/Site: Solvents and Petroleum

Lab Sample ID: 480-53428-9

**Client Sample ID: TW-3** Date Collected: 01/16/14 14:00 Matrix: Solid

Date Received: 01/17/14 01:00 Percent Solids: 89.7

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Cyclohexane	ND		5.0		ug/Kg	<u></u>	01/23/14 10:41	01/23/14 16:55	1
Dichlorodifluoromethane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
Ethylbenzene	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:55	1
1,2-Dibromoethane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
Isopropylbenzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
Methyl acetate	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
Methyl tert-butyl ether	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 16:55	1
Methylcyclohexane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
Methylene Chloride	17		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:55	1
Styrene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
Tetrachloroethene	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:55	1
Toluene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
trans-1,2-Dichloroethene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
trans-1,3-Dichloropropene	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 16:55	1
Trichloroethene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
Trichlorofluoromethane	ND		5.0		ug/Kg	\$	01/23/14 10:41	01/23/14 16:55	1
Vinyl chloride	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
Xylenes, Total	ND		10		ug/Kg	₽	01/23/14 10:41	01/23/14 16:55	1
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	98		71 - 125				01/23/14 10:41	01/23/14 16:55	1
1,2-Dichloroethane-d4 (Surr)	98		64 - 126				01/23/14 10:41	01/23/14 16:55	1
4-Bromofluorobenzene (Surr)	100		72 - 126				01/23/14 10:41	01/23/14 16:55	1

Client Sample ID: TW-4 Lab Sample ID: 480-53428-10 Date Collected: 01/16/14 15:25 **Matrix: Solid** Date Received: 01/17/14 01:00 Percent Solids: 88.1

Analyte	Result Quali	ifier RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND	5.0		ug/Kg	<del></del>	01/23/14 10:41	01/23/14 17:21	1
1,1,2,2-Tetrachloroethane	ND	5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 17:21	1
1,1,2-Trichloroethane	ND	5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 17:21	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND	5.0		ug/Kg	\$	01/23/14 10:41	01/23/14 17:21	1
1,1-Dichloroethane	ND	5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 17:21	1
1,1-Dichloroethene	ND	5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 17:21	1
1,2,4-Trichlorobenzene	ND	5.0		ug/Kg	\$	01/23/14 10:41	01/23/14 17:21	1
1,2-Dibromo-3-Chloropropane	ND	5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 17:21	1
1,2-Dichlorobenzene	ND	5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 17:21	1
1,2-Dichloroethane	ND	5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
1,2-Dichloropropane	ND	5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 17:21	1
1,3-Dichlorobenzene	ND	5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 17:21	1
1,4-Dichlorobenzene	ND	5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 17:21	1
2-Butanone (MEK)	ND	25		ug/Kg	₩	01/23/14 10:41	01/23/14 17:21	1
2-Hexanone	ND	25		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
4-Methyl-2-pentanone (MIBK)	ND	25		ug/Kg	₩.	01/23/14 10:41	01/23/14 17:21	1
Acetone	ND	25		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
Benzene	ND	5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 17:21	1
Bromodichloromethane	ND	5.0		ug/Kg	\$	01/23/14 10:41	01/23/14 17:21	1
Bromoform	ND	5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1

TestAmerica Buffalo

TestAmerica Job ID: 480-53428-2

Client: CHA Inc

Project/Site: Solvents and Petroleum

Date Received: 01/17/14 01:00

4-Bromofluorobenzene (Surr)

**Client Sample ID: TW-4** Lab Sample ID: 480-53428-10 Date Collected: 01/16/14 15:25

Matrix: Solid

TestAmerica Job ID: 480-53428-2

Percent Solids: 88.1

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bromomethane	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 17:21	1
Carbon disulfide	ND		5.0		ug/Kg	\$	01/23/14 10:41	01/23/14 17:21	1
Carbon tetrachloride	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
Chlorobenzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
Dibromochloromethane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
Chloroethane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
Chloroform	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
Chloromethane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
cis-1,2-Dichloroethene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
cis-1,3-Dichloropropene	ND		5.0		ug/Kg	₩	01/23/14 10:41	01/23/14 17:21	1
Cyclohexane	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 17:21	1
Dichlorodifluoromethane	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
Ethylbenzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
1,2-Dibromoethane	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 17:21	1
Isopropylbenzene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
Methyl acetate	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
Methyl tert-butyl ether	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 17:21	1
Methylcyclohexane	ND		5.0		ug/Kg	☼	01/23/14 10:41	01/23/14 17:21	1
Methylene Chloride	16		5.0		ug/Kg	☼	01/23/14 10:41	01/23/14 17:21	1
Styrene	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 17:21	1
Tetrachloroethene	ND		5.0		ug/Kg	☼	01/23/14 10:41	01/23/14 17:21	1
Toluene	ND		5.0		ug/Kg	☼	01/23/14 10:41	01/23/14 17:21	1
trans-1,2-Dichloroethene	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 17:21	1
trans-1,3-Dichloropropene	ND		5.0		ug/Kg	☼	01/23/14 10:41	01/23/14 17:21	1
Trichloroethene	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
Trichlorofluoromethane	ND		5.0		ug/Kg		01/23/14 10:41	01/23/14 17:21	1
Vinyl chloride	ND		5.0		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
Xylenes, Total	ND		10		ug/Kg	₽	01/23/14 10:41	01/23/14 17:21	1
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
Toluene-d8 (Surr)	97		71 - 125				01/23/14 10:41	01/23/14 17:21	1
1,2-Dichloroethane-d4 (Surr)	101		64 - 126				01/23/14 10:41	01/23/14 17:21	1

72 - 126

102

# **Surrogate Summary**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-2

Method: 8260C - Volatile Organic Compounds by GC/MS

Matrix: Solid Prep Type: Total/NA

				Percent Surro	gate Recovery (Acceptance Limits)
		TOL	12DCE	BFB	
Lab Sample ID	Client Sample ID	(71-125)	(64-126)	(72-126)	
480-53428-7	TW-1	99	100	104	
480-53428-8	TW-2	98	99	100	
180-53428-9	TW-3	98	98	100	
80-53428-10	TW-4	97	101	102	
.CS 480-162927/6	Lab Control Sample	98	98	103	
MB 480-162927/7	Method Blank	98	95	99	

TOL = Toluene-d8 (Surr)

12DCE = 1,2-Dichloroethane-d4 (Surr)

BFB = 4-Bromofluorobenzene (Surr)

3

4

5

7

8

11

14

# **QC Sample Results**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-2

# Method: 8260C - Volatile Organic Compounds by GC/MS

Lab Sample ID: MB 480-162927/7

Matrix: Solid

Analysis Batch: 162927

Client Sample ID: Method Blank **Prep Type: Total/NA** 

Analyte		MB Qualifier	RL	MDL Unit	D	Prepared	Analyzed	Dil Fac
1,1,1-Trichloroethane	ND		5.0	ug/Kg		riepaieu	01/23/14 12:27	1
1,1,2,2-Tetrachloroethane	ND		5.0	ug/Kg			01/23/14 12:27	1
1,1,2-Trichloroethane	ND		5.0	ug/Kg			01/23/14 12:27	1
1,1,2-Trichloro-1,2,2-trifluoroethane	ND		5.0	ug/Kg			01/23/14 12:27	· · · · · · · · · · · · · · · · · · ·
1,1-Dichloroethane	ND		5.0	ug/Kg			01/23/14 12:27	1
1,1-Dichloroethene	ND		5.0	ug/Kg			01/23/14 12:27	1
1,2,4-Trichlorobenzene	ND		5.0	ug/Kg			01/23/14 12:27	
1,2-Dibromo-3-Chloropropane	ND ND		5.0	ug/Kg ug/Kg			01/23/14 12:27	1
1,2-Dibromo-3-Chioroproparie	ND ND		5.0	ug/Kg			01/23/14 12:27	1
							01/23/14 12:27	
1,2-Dichloroethane	ND ND		5.0 5.0	ug/Kg			01/23/14 12:27	1
1,2-Dichloropropane	ND ND			ug/Kg				
1,3-Dichlorobenzene			5.0	ug/Kg			01/23/14 12:27	1
1,4-Dichlorobenzene	ND		5.0	ug/Kg			01/23/14 12:27	1
2-Butanone (MEK)	ND		25	ug/Kg			01/23/14 12:27	1
2-Hexanone	ND		25	ug/Kg			01/23/14 12:27	1
4-Methyl-2-pentanone (MIBK)	ND		25	ug/Kg			01/23/14 12:27	1
Acetone	ND		25	ug/Kg			01/23/14 12:27	1
Benzene	ND		5.0	ug/Kg			01/23/14 12:27	1
Bromodichloromethane	ND		5.0	ug/Kg			01/23/14 12:27	1
Bromoform	ND		5.0	ug/Kg			01/23/14 12:27	1
Bromomethane	ND		5.0	ug/Kg			01/23/14 12:27	1
Carbon disulfide	ND		5.0	ug/Kg			01/23/14 12:27	1
Carbon tetrachloride	ND		5.0	ug/Kg			01/23/14 12:27	1
Chlorobenzene	ND		5.0	ug/Kg			01/23/14 12:27	1
Dibromochloromethane	ND		5.0	ug/Kg			01/23/14 12:27	1
Chloroethane	ND		5.0	ug/Kg			01/23/14 12:27	1
Chloroform	ND		5.0	ug/Kg			01/23/14 12:27	1
Chloromethane	ND		5.0	ug/Kg			01/23/14 12:27	1
cis-1,2-Dichloroethene	ND		5.0	ug/Kg			01/23/14 12:27	1
cis-1,3-Dichloropropene	ND		5.0	ug/Kg			01/23/14 12:27	1
Cyclohexane	ND		5.0	ug/Kg			01/23/14 12:27	1
Dichlorodifluoromethane	ND		5.0	ug/Kg			01/23/14 12:27	1
Ethylbenzene	ND		5.0	ug/Kg			01/23/14 12:27	1
1,2-Dibromoethane	ND		5.0	ug/Kg			01/23/14 12:27	1
Isopropylbenzene	ND		5.0	ug/Kg			01/23/14 12:27	1
Methyl acetate	ND		5.0	ug/Kg			01/23/14 12:27	1
Methyl tert-butyl ether	ND		5.0	ug/Kg			01/23/14 12:27	1
Methylcyclohexane	ND		5.0	ug/Kg			01/23/14 12:27	1
Methylene Chloride	ND		5.0	ug/Kg			01/23/14 12:27	1
Styrene	ND		5.0	ug/Kg			01/23/14 12:27	1
Tetrachloroethene	ND		5.0	ug/Kg			01/23/14 12:27	1
Toluene	ND		5.0	ug/Kg			01/23/14 12:27	1
trans-1,2-Dichloroethene	ND		5.0	ug/Kg			01/23/14 12:27	· · · · · · · · · · · · · · · · · · ·
trans-1,3-Dichloropropene	ND ND		5.0	ug/Kg ug/Kg			01/23/14 12:27	1
Trichloroethene	ND ND		5.0				01/23/14 12:27	
				ug/Kg				1
Trichlorofluoromethane	ND		5.0	ug/Kg			01/23/14 12:27	1
Vinyl chloride	ND		5.0	ug/Kg			01/23/14 12:27	1
Xylenes, Total	ND		10	ug/Kg			01/23/14 12:27	1

TestAmerica Buffalo

# **QC Sample Results**

Client: CHA Inc

**Matrix: Solid** 

Matrix: Solid

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-2

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyzed 01/23/14 12:27 01/23/14 12:27 01/23/14 12:27

Prepared

Analysis Batch: 162927

Lab Sample ID: LCS 480-162927/6

Lab Sample ID: MB 480-162927/7

	МВ	МВ	
Surrogate	%Recovery	Qualifier	Limits
Toluene-d8 (Surr)	98		71 - 125
1,2-Dichloroethane-d4 (Surr)	95		64 - 126
4-Bromofluorobenzene (Surr)	99		72 - 126

Method: 8260C - Volatile Organic Compounds by GC/MS (Continued)

Client Sample ID: Lab Control Sample Prep Type: Total/NA

Analysis Batch: 162927

	Spike	LCS	LCS				%Rec.	
Analyte	Added	Result	Qualifier	Unit	D	%Rec	Limits	
1,1-Dichloroethane	50.0	47.1		ug/Kg		94	73 - 126	
1,1-Dichloroethene	50.0	45.7		ug/Kg		91	59 <sub>-</sub> 125	
1,2-Dichlorobenzene	50.0	48.4		ug/Kg		97	75 <sub>-</sub> 120	
1,2-Dichloroethane	50.0	49.5		ug/Kg		99	77 - 122	
Benzene	50.0	47.1		ug/Kg		94	79 <sub>-</sub> 127	
Chlorobenzene	50.0	46.7		ug/Kg		93	76 - 124	
cis-1,2-Dichloroethene	50.0	48.2		ug/Kg		96	81 _ 117	
Ethylbenzene	50.0	46.9		ug/Kg		94	80 - 120	
Methyl tert-butyl ether	50.0	50.4		ug/Kg		101	63 - 125	
Tetrachloroethene	50.0	44.9		ug/Kg		90	74 - 122	
Toluene	50.0	45.9		ug/Kg		92	74 - 128	
trans-1,2-Dichloroethene	50.0	46.4		ug/Kg		93	78 <sub>-</sub> 126	
Trichloroethene	50.0	44.4		ug/Kg		89	77 <sub>-</sub> 129	

LCS LCS Surrogate %Recovery Qualifier Limits Toluene-d8 (Surr) 98 71 - 125 1,2-Dichloroethane-d4 (Surr) 98 64 - 126 4-Bromofluorobenzene (Surr) 103 72 - 126

Dil Fac

# **QC Association Summary**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-2

### **GC/MS VOA**

### Analysis Batch: 162927

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
480-53428-7	TW-1	Total/NA	Solid	8260C	162943
480-53428-8	TW-2	Total/NA	Solid	8260C	162943
480-53428-9	TW-3	Total/NA	Solid	8260C	162943
480-53428-10	TW-4	Total/NA	Solid	8260C	162943
LCS 480-162927/6	Lab Control Sample	Total/NA	Solid	8260C	
MB 480-162927/7	Method Blank	Total/NA	Solid	8260C	

### **Prep Batch: 162943**

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
480-53428-7	TW-1	Total/NA	Solid	5035A	
480-53428-8	TW-2	Total/NA	Solid	5035A	
480-53428-9	TW-3	Total/NA	Solid	5035A	
480-53428-10	TW-4	Total/NA	Solid	5035A	

### **General Chemistry**

### Analysis Batch: 162976

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
480-53428-7	TW-1	Total/NA	Solid	Moisture	
480-53428-8	TW-2	Total/NA	Solid	Moisture	
480-53428-9	TW-3	Total/NA	Solid	Moisture	
480-53428-10	TW-4	Total/NA	Solid	Moisture	

0

4.0

11

4.0

14

### **Lab Chronicle**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-2

Client Sample ID: TW-1	Lab Sample ID: 480-53428-7
Date Collected: 01/16/14 09:30	Matrix: Solid
Date Received: 01/17/14 01:00	Percent Solids: 88.0

	Batch	Batch		Dilution	Batch	Prepared		
Prep Type	Type	Method	Run	Factor	Number	or Analyzed	Analyst	Lab
Total/NA	Prep	5035A			162943	01/23/14 10:41	PJQ	TAL BUF
Total/NA	Analysis	8260C		1	162927	01/23/14 16:03	CDC	TAL BUF
Total/NA	Analysis	Moisture		1	162976	01/23/14 12:56	PJQ	TAL BUF

Client Sample ID: TW-2 Lab Sample ID: 480-53428-8 Date Collected: 01/16/14 11:45 **Matrix: Solid** 

Date Received: 01/17/14 01:00 Percent Solids: 84.1

	Batch	Batch		Dilution	Batch	Prepared		
Prep Type	Туре	Method	Run	Factor	Number	or Analyzed	Analyst	Lab
Total/NA	Prep	5035A			162943	01/23/14 10:41	PJQ	TAL BUF
Total/NA	Analysis	8260C		1	162927	01/23/14 16:29	CDC	TAL BUF
Total/NA	Analysis	Moisture		1	162976	01/23/14 12:56	PJQ	TAL BUF

**Client Sample ID: TW-3** Lab Sample ID: 480-53428-9

Date Collected: 01/16/14 14:00 **Matrix: Solid** Date Received: 01/17/14 01:00 Percent Solids: 89.7

	Batch	Batch		Dilution	Batch	Prepared		
Prep Type	Type	Method	Run	Factor	Number	or Analyzed	Analyst	Lab
Total/NA	Prep	5035A			162943	01/23/14 10:41	PJQ	TAL BUF
Total/NA	Analysis	8260C		1	162927	01/23/14 16:55	CDC	TAL BUF
Total/NA	Analysis	Moisture		1	162976	01/23/14 12:56	PJQ	TAL BUF

Client Sample ID: TW-4 Lab Sample ID: 480-53428-10

Date Collected: 01/16/14 15:25 **Matrix: Solid** Date Received: 01/17/14 01:00 Percent Solids: 88.1

	Batch	Batch		Dilution	Batch	Prepared		
Prep Type	Туре	Method	Run	Factor	Number	or Analyzed	Analyst	Lab
Total/NA	Prep	5035A			162943	01/23/14 10:41	PJQ	TAL BUF
Total/NA	Analysis	8260C		1	162927	01/23/14 17:21	CDC	TAL BUF
Total/NA	Analysis	Moisture		1	162976	01/23/14 12:56	PJQ	TAL BUF

### Laboratory References:

TAL BUF = TestAmerica Buffalo, 10 Hazelwood Drive, Amherst, NY 14228-2298, TEL (716)691-2600

# **Certification Summary**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-2

### Laboratory: TestAmerica Buffalo

Unless otherwise noted, all analytes for this laboratory were covered under each certification below.

Authority	Program		EPA Region	Certification ID	Expiration Date
New York	NELAP		2	10026	03-31-14
The following analytes	are included in this report, bu	it certification is not offe	ered by the governing a	authority:	
Analysis Method	Prep Method	Matrix	Analyt	e	
Analysis Method Moisture	Prep Method	Matrix Solid		nt Moisture	

5

6

Я

10

11

13

14

# **Method Summary**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-2

Method	Method Description	Protocol	Laboratory
8260C	Volatile Organic Compounds by GC/MS	SW846	TAL BUF
Moisture	Percent Moisture	EPA	TAL BUF

### Protocol References:

EPA = US Environmental Protection Agency

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

### Laboratory References:

TAL BUF = TestAmerica Buffalo, 10 Hazelwood Drive, Amherst, NY 14228-2298, TEL (716)691-2600

6

Δ

5

0

o

9

- 0

13

14

# **Sample Summary**

Client: CHA Inc

Project/Site: Solvents and Petroleum

TestAmerica Job ID: 480-53428-2

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
480-53428-7	TW-1	Solid	01/16/14 09:30	01/17/14 01:00
480-53428-8	TW-2	Solid	01/16/14 11:45	01/17/14 01:00
480-53428-9	TW-3	Solid	01/16/14 14:00	01/17/14 01:00
480-53428-10	TW-4	Solid	01/16/14 15:25	01/17/14 01:00

2

4

a

10

13

14



and later and la	Sampler:		1. 4	Lab PM	A:		-			Carrier	Carrier Tracking No(s):		COC No:	7 0017	Г
Client Contact	<b>∟</b> I	7		Gray-r F-Mail	Gray-Erdmann, reggy E-Mail	in, reg	gy J						480-43507-	11/62.1	Т
Katie Fleet McMCK	215	380,7	733)	pegg	y.gray-e	rdman	peggy.gray-erdmann@testamericainc.com	mericair	IC.com				Page 1 of 1		_
Company: CHA Inc							1	Analysis Requested	is Rec	lueste	p		, # doL		
Address: 441 South Salina Street	Due Date Requested:	:pe							-				Preservation Codes		Г
City. Syracuse	TAT Requested (days):	1						CI_E		1	JUI.		B - NaOH C - Zn Acetate	M - Texane N - None O - AsNaO2	
State, Zlp: NY, 13202	5	g	1					M4500			odo.		D - Nitric Acid E - NaHSO4		
Phone:	PO# 8423.2010.44000	0			(0	_		S ,əls		, ,	bin		G - Amchlor H - Ascorbic A		
Email: kflood@chacompanies.com	:# OM					nodr	Я	trate			d t				
Project Name: Solvents and Petroleum	Project #: 48004389	}								00	101		THE RESIDENCE	W - pn 4-5 Z - other (specify)	
Site:	SSOW#:									35	L 8		of co		
		Sample	Sample Type (C=comp.	Watrix (W=water, S=solid, O=wasteloll, BT=Ticsto	id Filtered S MS/M mof	0C, 6020A, S	1600_S2_D -	363.2_Nit	.2 - Alkalinity 0_FE_D - Fe	5701	1918		al Number		100
Sample Identification	Sample Date		G=grab)	A=Air)			-	-	-	٨	E .			Special Instructions/Note:	4
	$\bigvee$	X	Preservation Code	ion Code:	Ž	A O	A CB	z	z						
MW-1S	1110114	1700	0	Water		メメ	X	X	XX		X		31013	3 Samprd 13.	35
MW-4R	1116114	1522	6	Water		X	·× ·×	×	ХX		· X				
THU !	41/2011	1320	6	Water						×			3	2	
TKW 2	-	1400	5	where						×			3 / MW	15, MW-4	3
Tw 3		1530	5	Water						×			3 6-W	Samo's back	~
1 m 7		1550	2	whi						メ			3 privit	it specific RL	S
) W		930	و	Soil						×			2 2	_ <	7
1.WZ		1145	ئ	118						×			7		
T.W.3		1400	3	Soil		-	- 24			×			7		
1221	<b>&gt;</b>	1525	ę	1.8				11		X	102		2		
The Blank							×		_						_
Possible Hazard Identification					Sam	ple Dis	posal (	A fee n	ay be	ssess	ed if sample	es are re	Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)	han 1 month)	
Deliverable Requested: I, II, III, IV, Other (specify)			Kadiological		Spec	ial Inst	Special Instructions/QC Requirements	AC Re	quireme	nts:	ments:		Archive ror	Months	Τ
Empty Kit Relinquished by:		Date:			Time:			١		Σ	Method of Shipment:	ent:			Т
TION AND MADE OF THE PROPERTY	Date/Time:	CITA		Company	L.	Received	N X	1	1	1	Date	Date/Time:	1,17.00	> KS /	T
	Date/Time: 19	6/	5	Company	- 1	Received	py:	1	7	١,	Date	Date/Time:	1 010	Company	
	Date/Time:		1.83	Company	IE.	Received by:	by:				Date/	Date/Time:		Company	
Custody Seals Intact: Custody Seal No.:  A Yes A No					Ü	Cooler Te	Cooler Temperature(s) °C and Other Remarks:	(s) °C and	Other Re	emarks:	7	7	× 5 # 5		1
				1	1				1	9	8	-	5		1

Chain of Custody Record

# **Login Sample Receipt Checklist**

Client: CHA Inc Job Number: 480-53428-2

Login Number: 53428 List Source: TestAmerica Buffalo

List Number: 1

Creator: Wienke, Robert K

Creator: Wienke, Robert K		
Question	Answer	Comment
Radioactivity either was not measured or, if measured, is at or below background	True	
The cooler's custody seal, if present, is intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the sample IDs on the containers and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
VOA sample vials do not have headspace or bubble is <6mm (1/4") in diameter.	True	
If necessary, staff have been informed of any short hold time or quick TAT needs	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Sampling Company provided.	True	CHA
Samples received within 48 hours of sampling.	True	
Samples requiring field filtration have been filtered in the field.	N/A	
Chlorine Residual checked.	N/A	

FOIL199460 1/24/2014

